

To: 1 040735 2-9  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-007-22,271-00-00 22 R  
100' N of  
C NW, SEC. 17, T 35 S, R 13 W/X  
4060 feet from S section line  
3960 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5171

Lease Name Bouziden Well # B-1

Operator: Marathon Oil Corp.

County Barber

Name & Address RR 1, Box 25

Well Total Depth 5250 feet

Medicine Lodge, KS 67104

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 390

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Clarke Corporation License Number 5105

Address P.O. Box 187, Medicine Lodge, KS

Company to plug at: Hour: 1:30 p.m. Day: 9 Month: 2 Year: 1993

Plugging proposal received from Jeff Sletto

(company name) Clarke Corporation (phone) 316-886-5665

were: 4 1/2" at 5136' w/150 sx cement, PBDT 5025', Perfs at 4923-93'

1st plug sand back to 4875' and dump 4 sx cement on top of sand through bailer,

2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8" wiper plug and pump 100. sx cement.

RECEIVED  
CLARKE CORPORATION  
COMMISSION

FEB 1 - 1993

Plugging Proposal Received by Steve Pfeifer

(TECHNICIAN)  
WICHITA, KS  
DIVISION

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 2 p.m. Day: 9 Month: 2 Year: 1993

ACTUAL PLUGGING REPORT 1st plug sanded back to 4875' and dumped 4 sx cement on top of sand bridge through bailer,

2nd plug pumped down 8 5/8" surface pipe with 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, released 8 5/8" wiper plug and pumped 100 sx cement.

Maximum pressure 400 psi and shut in 250 psi.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 3800' of 4 1/2" casing.  
(If additional description is necessary, use BACK of this form.)

**INVOLVED**

I did  observe this plugging.

DATE 2-22-93

Signed Stephen J Pfeifer  
(TECHNICIAN)

INV. NO. 37410