

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-007-00081-00-01
Spot: SEWNNE Sec/Twnshp/Rge: 32-34S-12W
4290 feet from S Section Line, 1650 feet from E Section Line
Lease/Unit Name: GRAVES D Well Number: 1
County: BARBER Total Vertical Depth: 4807 feet

Operator License No.: 31881

Conductor Pipe: Size feet:

Op Name: MCGINNESS OIL COMPANY OF KANSAS Surface Casing: Size 8.625 feet: 320

Address: 150 N. MAIN, STE 1026
WICHITA, KS 67202

Production: Size 5.5 feet: 4800

Liner: Size feet:

\$156.23

Well Type: GAS

UIC Docket No:

Date/Time to Plug: 08/29/2001 6:00 PM

Plug Co. License No.: 5893

Plug Co. Name: PRATT WELL SERVICE, INC.

Proposal Rcvd. from: STEVE HART

Company: PRATT WELL SERVICE, INC.

Phone: (316) 672-2531

Proposed Plugging Method: CIBP @ 4630' & 2 SX CMT. 1ST PLUG AT 600' WITH 50 SX CMT. 2ND PLUG AT 340' WITH 50 SX CMT. 3RD PLUG AT 0-40' WITH 10 SX CMT.

Plugging Proposal Received By: SCOTT ALBERG

Witness Type: Plugging Operations 100% Witnessed (Complete)

Date/Time Plugging Completed: 08/29/2001 8:00 PM

KCC Agent: SCOTT ALBERG

Actual Plugging Report:


PBTD 4800'. PERFS AT 4681-4687'. CIBP @ 4650' & 2 SX CMT ON TOP WITH BAILER. 1ST PLUG SPOT 50 SX CMT AT 326'. 2ND PLUG SPOT 65 SX CMT AT 0-40'. GOOD CIRCULATION ON FIRST PLUG, POOR CIRCULATION ON TOP PLUG AT FIRST, THEN GOOD AT END OF JOB.

Remarks: USED 60/40 POZMIX 6% GEL BY ALLIED. RECOVERED 3018' OF 5 1/2" CASING.

Plugged through: CSG

District: 01

Signed



(TECHNICIAN)

RECEIVED
9-6-01
SEP 06 2001

INVOICED

AUG 31 2001

DATE

9-6-01

KCC WICHITA

INV. NO. 2002060358

Form CP-28 