

1041201
STATE CORPORATION COMMISSION
Wichita State Office Bldg. - PLUGGING SECTION
130 S. Market, Room 2078
Wichita, KS 67202

API NUMBER 15-007-21,761-0000
SE SW NE, SEC. 32, T 34 S, R 12 W/E
2970 feet from S section line
1650 feet from E section line

8-15
TECHNICIAN'S PLUGGING REPORT

Operator License # 5255
Operator: McGinness Oil Company
Name:
Address 150 N. Main, Ste. 1026
Wichita, KS 67202

Lease Name Allen Hall Well # 2
County Barber 171.60
Well Total Depth 5280 feet
Conductor Pipe: Size feet
Surface Casing: Size 8 5/8 feet 353

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Clarke Corporation License Number 5105

Address P.O. Box 187, Medicine Lodge, KS 67104

Company to plug at: Hour: 10:30 a.m. Day: 15 Month: 8 Year: 19 96

Plugging proposal received from Alan Vratil

(company name) Clarke Corporation (phone) 316-886-5665

Work: 5 1/2" at 4950' w/200 sx cement, PBTD 4929', Perfs at 4777-83, 4800-14, 4842-54'

1st plug sand back to 4750' and dump 5 sx cement on top of sand through bailer,
2nd plug pump 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, release.
8 5/8" wiper plug and pump 100 sx cement.

Plugging Proposal Received by Steve Middleton
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 11:15 a.m. Day: 15 Month: 8 Year: 19 96

ACTUAL PLUGGING REPORT 1st plug sanded back to 4630' and dumped 5 sx cement on top of sand
bridge through bailer,

2nd plug pumped down 8 5/8" surface pipe with 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, released 8 5/8" wiper plug and pumped 100 sx cement.

Maximum pressure 500 psi and shut in 100 psi.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 3400' of 5 1/2" casing.
(If additional description is necessary, use BACK of this form.)

INVOICED
Observe this plugging.

DATE AUG 28 1996

NUMBER 43674

Signed Stephen J. Deifer
(TECHNICIAN)

K.G.S. LIBRARY

GEARHART

DUAL INDUCTION
LATEROLOG

15-007-21761-0008

FILING NO.	COMPANY	SUN WEST EXPLORATION	
	WELL	ALLEN HALL NO. 2	RELEASED NO SMALL SCALE
	FIELD	NORTH HAPDTNER	
	COUNTY	BARBER	STATE KANSAS
LOCATION:		SE SW NE	Other Service DDL/CNS/GR WEL
SEC		32	TWP 34S RGE 12W

Permanent Datum	GL	Elev.	1433	Elev.: K.B.	14
Log Measured from	KB	10	Ft. Above Perm. Datum	D.F.	-
Drilling Measured from	KB			G.L.	14

Date	2-16-84				
Run No.	One				
Depth-Driller	5280				
Depth-Logger	5275				
Bottom Logged Interval	5273				
Top Logged Interval	352				
Casing-Driller	8	5/8 @ 350			
Casing-Logger	352				
Bit Size	7 7/8				
Type Fluid in Hole	Chem. Gel				
Density	Viscosity	9.3	42		
ph	Fluid Loss	7.5	14.2cc	cc	cc
Source of Sample	Flowline				
Rm @ Meas. Temp.	.45 @ 52 °F				
Rmf @ Meas. Temp.	.34 @ 52 °F				
Rmc @ Meas. Temp.	.50 @ 52 °F				
Source of Rmf	Rmc	C	C		
Rm @ BHT	.21 @ 123 °F				
Time	End Circulation	1800 Hours			
	Logger on bottom	2123 Hours			
Max. Rec. Temp. Deg. F.	123 °F				
Equip. No.	Location	7553	Wichita		
Recorded By	Walton				
Witnessed By	Mr. McGinness				

K.G.S. LIBRARY