

3-23 15-007-01082-0000 214

1 040254  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- NA  
NW  
C NE SE, SEC. 32, T 34 S, R 12 W 4E  
1980 feet from S section line  
660 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5364

Lease Name Sterling Well # 1

Operator: Beren Corporation

County Barber 156.26

Name: Address Box 723

Well Total Depth 4808 feet

Hays, KS 67601

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 261

Abandoned Oil Well Gas Well X Input Well SWD Well O&A

Other well as hereinafter indicated

Plugging Contractor Clarke Corporation License Number 5105

Address P.O. Box 187, Medicine Lodge, KS 67104

Company to plug at: Hour: 9:45 a.m. Day: 23 Month: 3 Year: 19 89

Plugging proposal received from Elmo Morgenstern

(company name) Clarke Corporation (phone) 316-886-5665

were: 5 1/2" at 4808' PBSD 4800' Perfs at 4735-50, 4768-86'

1st plug sanded back to 4685' and dump 5 sx cement on top of sand through bailer,

2nd plug pump 4 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8" wiper plug and pump 100 sx cement.

RECEIVED  
STATE CORPORATION COMMISSION  
3-28-89  
MAR 28 1989  
CONSERVATION DIVISION  
Wichita, Kansas

Plugging Proposal Received by Duane Rankin (TECHNICIAN)

Plugging Operations attended by Agent?: All X Part None

Operations Hour: 10:15 a.m. Day: 23 Month: 3 Year: 19 89

ACTUAL PLUGGING REPORT 1st plug sanded back to 4680' and dumped 5 sx cement on top of sand bridge with bailer,

2nd plug pumped down 8 5/8" surface pipe with 400 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls and 100 sx cement.

Maximum pressure 400 psi and shut in 150 spi.

Remarks: Used 60/40 Pozmix 2% gel 2% cc by B.J. Titan. Recovered 3000' of 5 1/2" casing. (If additional description is necessary, use BACK of this form.)

INVOICED

DATE 3-30-89

INV. NO. 24289

Signed Stephen J. Puffer (TECHNICIAN)