

5-10-88

To: 1 040095
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 007- 21398 ~~21,298~~ ~~0000~~

SW NE SE, SEC. 28, T 34 S, R 12 W ~~EX~~
1650 feet from S section line
990 feet from E section line

TECHNICIAN'S PLUGGING REPORT
Operator License # 5042

Lease Name Graves "B" Well # 3
County Barber 155.03

Operator: Edmiston Oil Company, Inc.
Name & Address 1260 Kansas State Bank Bldg.
Wichita, KS 67202

Well Total Depth 4770 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 311

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pulling License Number 6050

Address Box 347, Chase, KS 67524

Company to plug at: Hour: 2:30 a.m. Day: 10 Month: 5 Year: 19 88

Plugging proposal received from Millard Kelso

(company name) Kelso Casing Pulling (phone) 316-938-2457

were: 4 1/2" at 4769' Perfs at 4710-20'

1st plug sand back to 4660' and dump 4 sx cement on top of sand through bailer,

2nd plug pump 4 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8"

wiper plug and pump 130 sx cement.

Plugging Proposal Received by Paul A. Luthi
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 3:15 p.m. Day: 10 Month: 5 Year: 19 88

ACTUAL PLUGGING REPORT 1st plug sanded back to 4660' and dumped 4 sx cement on top
of sand through bailer,

2nd plug pumped down 8 5/8" with 400 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel,

100 lbs. hulls, released 8 5/8" wiper plug and pumped 100 sx cement.

Maximum pressure 400 psi and shut in 200 psi.

Remarks: Used 60/40 Pozmix 6% gel by B.J. Titan. Recovered 3444' of 4 1/2" casing.
(if additional description is necessary, use BACK of this form.)

RECEIVED
STATE CORPORATION COMMISSION
5-13-88
MAY 13 1989

CONSERVATION DIVISION
Wichita, Kansas

INVOICED

DATE 5-17-88

INV. NO. 20631

Signed Stephan J. Pfeifer
(TECHNICIAN)