

To: 1 040067
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

TECHNICIAN'S PLUGGING REPORT

Operator License # 5042

Operator: Edmiston Oil Company, Inc.
Name &
Address 1260 Kansas State Bank Bldg.
Wichita, KS 67202

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pulling License Number 6050

Address Box 347, Chase, KS 67524

Company to plug at: Hour: 11:45 a.m. Day: 15 Month: 3 Year: 19 88

Plugging proposal received from Millard Kelso

(company name) Kelso Casing Pulling (phone) 316-938-2457

were: 4½" at 4799' Perfs at 4742-48'

1st plug sand back to 4690' and dump 4 sx cement on top of sand through bailer,

2nd plug pump down 8 5/8" with 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel,

100 lbs. hulls, release 8 5/8" wiper plug and pump 100 sx cement.

Plugging Proposal Received by Steve Pfeifer
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 12:15 p.m. Day: 15 Month: 3 Year: 19 88

ACTUAL PLUGGING REPORT 1st plug sanded back to 4690' and dumped 4 sx cement on top of
sand through bailer,

2nd plug pumped down 8 5/8" with 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel,

100 lbs. hulls, released 8 5/8" wiper plug and pumped 100 sx cement.

Maximum pressure 450 psi and shut in 300 psi.

Remarks: Used 60/40 Pozmix 6% gel by B.J. Titan. Recovered 3398' of 4½" casing.

(If additional description is necessary, use BACK of this form.)

INVOICED
Observe this plugging.

DATE 3-25-88

INV. NO. 20187

Signed Steve Pfeifer
(TECHNICIAN)

3-15-88 TMB-ECC
2188-0000
API NUMBER 15-007-21,379
SW SE SE, SEC. 28, T 34 S, R 12 W/E
330 feet from S section line
990 feet from E section line
Lease Name Graves "B" Well # 2
County Barber 156.00
Well Total Depth 4800 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 366

RECEIVED
STATE CORPORATION COMMISSION

3-23-88

MAR 23 1988

CONSERVATION DIVISION
Wichita, Kansas