

To: 1 041200  
STATE CORPORATION COMMISSION  
Wichita State Office Bldg. - PLUGGING SECTION  
130 S. Market, Room 2078  
Wichita, KS 67202

API NUMBER 15- 007-21,579-0000  
E/2 SW SW, SEC. 28, T 34 S, R 12 W  
660 feet from S section line  
4290 feet from E section line

8-15  
TECHNICIAN'S PLUGGING REPORT

Operator License # 5255  
Operator: McGinness Oil Company  
Name & Address: 150 N. Main, Ste. 1026  
Wichita, KS 67202

Lease Name Graves B Well # 1  
County Barber 159.12  
Well Total Depth 4896 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 feet 326

Abandoned Oil Well  Gas Well  Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Clarke Corporation License Number 5105  
Address P.O. Box 187, Medicine Lodge, KS 67104

Company to plug at: Hour: 12:15 p.m. Day: 15 Month: 8 Year: 19 96

Plugging proposal received from Alan Vratil  
(company name) Clarke Corporation (phone) 316-886-5665

Work: 4 1/2" at 4895' w/175 sx cement, PBD 4889', Perfs at 4809-17, 4822-28, 4832-52'  
1st plug sand back to 4750' and dump 4 sx cement on top of sand through bailer,  
2nd plug pump 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, release  
8 5/8" wiper plug and pump 100 sx cement.

Plugging Proposal Received by Kevin Strube (TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_  
Operations Completed: Hour: 1 p.m. Day: 15 Month: 8 Year: 19 96

ACTUAL PLUGGING REPORT 1st plug sanded back to 4690' and dumped 4 sx cement on top of sand  
bridge through bailer,  
2nd plug pumped down 8 5/8" with 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100  
lbs. hulls, released 8 5/8" wiper plug and pumped 100 sx cement.  
Maximum pressure 250 psi and shut in 150 psi.

RECEIVED  
STATE CORPORATION COMMISSION

AUG 22 1996  
8-22-96

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 3500' of 4 1/2" casing.  
(If additional description is necessary, use BACK of this form.)

INVOICED

DATE AUG 28 1996  
INV. NO. 43673

Signed Stephen J. Penzler (TECHNICIAN)

