

1 040322

9-20

81 R

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-007-21,159-0000
SE SW NW, SEC. 27, T 34 S, R 12 W/E
2970 feet from S section line
4290 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5086

Lease Name Richardson B Well # 1

Operator: Pintail Petroleum, Ltd.
Name & Address 412 East Douglas, Suite One
Wichita, KS 67202

County Barber 157.43
Well Total Depth 4844 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 10 3/4 feet 310

Abandoned Oil Well _____ Gas Well Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Great Bend Casing Pullers, Inc. License Number 4635

Address Box 768, Great Bend, KS 67530

Company to plug at: Hour: 12 p.m. Day: 20 Month: 9 Year: 19 89

Plugging proposal received from Gary Burke

(company name) Great Bend Casing Pullers, Inc. (phone) 316-793-9711

were: 4 1/2" at 4844' PBTB 4820' Perfs at 4722-28'

1st plug sand back to 4670' and dump 4 sx cement on top of sand through bailer,

2nd plug pump 4 sx hulls, 10 sx gel, 50 sx cement, 6 sx gel, 1 sx hulls, and 125 sx cement.

Plugging Proposal Received by Steve Pfeifer
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 12:30 p.m. Day: 20 Month: 9 Year: 19 89

ACTUAL PLUGGING REPORT 1st plug sanded back to 4670' and dumped 4 sx cement on top of sand
bridge with bailer,

2nd plug pumped down 10 3/4" with 400 lbs. hulls, 10 sx gel, 50 sx cement, 6 sx gel,
100 lbs. hulls and 125 sx cement.

Maximum pressure 350 psi and shut in 100 psi.

RECEIVED
STATE CORPORATION COMMISSION
SEP 22 1989
9-22-89
CONSERVATION DIVISION
Wichita, Kansas

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 2594' of 4 1/2" casing.
(If additional description is necessary, use BACK of this form.)

INVOICED

DATE 9-28-89
INV. NO. 25977

Signed Stephen J. Pfeifer
(TECHNICIAN)