

1 040083

4-12-88

122
R

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-007-21,292-0000

SW SE SW, SEC. 27, T 34 S, R 12 W/E

330 feet from S section line

3630 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5042

Lease Name Burgess "A" Well # 1

Operator: Edmiston Oil Company, Inc.

County Barber 157.63

Name & Address 1260 Kansas State Bank Bldg.

Well Total Depth 4850 feet

Wichita, KS 67202

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 321

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ O&A _____

Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pulling License Number 6050

Address Box 347, Chase, KS 67524

Company to plug at: Hour: 4 p.m. Day: 12 Month: 4 Year: 19 88

Plugging proposal received from Millard Kelso

(company name) Kelso Casing Pulling (phone) 316-938-2457

were: 4 1/2" at 4849' PBD 4849' Perfs at 4740-56, 4764-4800'

1st plug sand back to 4690' and dump 4 sx cement on top of sand through bailer,

2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8" wiper plug and pump 100 sx cement.

Plugging Proposal Received by Steve Durrant
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 4:45 p.m. Day: 12 Month: 4 Year: 19 88

ACTUAL PLUGGING REPORT 1st plug sanded back to 4690' and dumped 4 sx cement on top of sand through bailer,

2nd plug pumped down 8 5/8" with 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, released 8 5/8" wiper plug and pumped 100 sx cement.

Maximum pressure 450 psi and shut in 200 psi.

Remarks: Used 60/40 Pozmix 6% gel by B.J. Titan. Recovered 3431' of 4 1/2" casing.
(if additional description is necessary, use BACK of this form.)

APR 20 1988
4-20-88
CONSERVATION DIVISION
Wichita, Kansas

INVOICED
(if desired) observe this plugging.

Signed Stephen J. Pfeifer
(TECHNICIAN)

DATE 4-26-88

INV. NO. 20445