

To: 1 040320
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-15-007-21377-00-01 9-20 80
Docket # D-21-129
SW SW SW, SEC. 27, T 34 S, R 12 W/E

TECHNICIAN'S PLUGGING REPORT

Operator License # 5086

Operator: Pintail Petroleum, Ltd.
Name & Address 412 East Douglas, Suite One
Wichita, KS 67202

Lease Name Burgess A Well # 2

County Barber 157.24

Well Total Depth 4838 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 305

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well X D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Great Bend Casing Pullers, Inc. License Number 4635

Address Box 768, Great Bend, KS 67530

Company to plug at: Hour: 10:15 a.m. Day: 20 Month: 9 Year: 19 89

Plugging proposal received from Gary Burke

(company name) Great Bend Casing Pullers, Inc. (phone) 316-793-9711

were: 4 1/2" at 4832' Perfs at 4770-80'

1st plug pump down 4 1/2" production casing with 26 sx ATL cement.

2nd plug pump down 4 1/2" X 8 5/8" annulus with 100 sx 60/40 Pozmix 6% gel.

Plugging Proposal Received by Steve Pfeifer
(TECHNICIAN)

Plugging Operations attended by Agent?: All X Part _____ None _____

Operations Completed: Hour: 11:15 a.m. Day: 20 Month: 9 Year: 19 89

ACTUAL PLUGGING REPORT 1st plug pumped down 4 1/2" production casing with 26 sx ATL cement.

Maximum pressure 1500 psi and shut in 950 psi.

2nd plug pumped down 4 1/2" X 8 5/8" annulus with 100 sx 60/40 Pozmix 6% gel.

Maximum pressure 100 psi and shut in 50 psi.

Junk in hole = 3100' of 2 3/8" tubing and packer & approx. 4150' of 1 1/2" OD _____
1 1/2" OD P.E. pipe top approx. 250' from surface.

2 3/8" tubing top 1500' from surface.

Remarks: Used ATL and 60/40 Pozmix 6% gel by Allied. No casing recovery, recovered 1500'
(If additional description is necessary, use BACK of this form.) of 2 3/8" tubing.

INVOICED 10/10/89 observe this plugging.

DATE 9-28-89

INV. NO. 25976

Signed Stephen J. Pfeifer
(TECHNICIAN)