

To: 1 040319
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

TECHNICIAN'S PLUGGING REPORT

Operator License # 5086

Operator: Pintail Petroleum, Ltd.
Name & Address 412 East Douglas, Suite One
Wichita, KS 67202

9-20 82 R
API NUMBER 15-007-21,396-0000

SW SW SE, SEC. 27, T 34 S, R 12 W/E

330 feet from S section line

2310 feet from E section line

Lease Name Burgess A Well # 3

County Barber 156.49

Well Total Depth 4815 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 315

Abandoned Oil Well Gas Well Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Great Bend Casing Pullers, Inc. License Number 4635

Address Box 768, Great Bend, KS 67530

Company to plug at: Hour: 8:45 a.m. Day: 20 Month: 9 Year: 1989

Plugging proposal received from Gary Burke

(company name) Great Bend Casing Pullers, Inc. (phone) 316-793-9711

were: 4 1/2" at 4814' PBSD 4800' Perfs at 4754-64'

1st plug sand back to 4700' and dump 4 sx cement on top of sand through bailer,

2nd plug pump 4 sx hulls, 10 sx gel, 50 sx cement, 6 sx gel, 1 sx hulls, release 8 5/8"

wiper plug and pump 100 sx cement.

Plugging Proposal Received by Steve Pfeifer
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None

Operations Completed: Hour: 9:15 a.m. Day: 20 Month: 9 Year: 1989

ACTUAL PLUGGING REPORT 1st plug sanded back to 4700' and dumped 4 sx cement on top of
sand bridge with bailer,

2nd plug pumped down 8 5/8" surface pipe with 400 lbs. hulls, 10 sx gel, 50 sx cement.

6 sx gel, 100 lbs. hulls, released 8 5/8" wiper plug and pumped 100 sx cement.

Maximum pressure 400 psi and shut in 100 psi.

RECEIVED
STATE CORPORATION COMMISSION

SEP 22 1989

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 2788' of 4 1/2" casing
(if additional description is necessary, use BACK of this form.) Wichita, Kansas

INVOICED
(if applicable) observe this plugging.

DATE 9-28-89

INV. NO. 25978

Signed Stephen J. Pfeifer
(TECHNICIAN)