

To: 1 051288  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

4-10  
API NUMBER 15- 007-21,397-~~0000~~  
SW SW SW, SEC. 26, T 34 S, R 12 W/E  
330 feet from S section line  
4950 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5552

Lease Name Burgess "B" Well # 3

Operator: Gore Oil Company

County Barber 157.30

Name:

Address: 125 North Market, Suite 1750

200 So. St. Francis  
Wichita, KS 67202 67201-2757

Well Total Depth 4840 feet

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 318

Abandoned Oil Well  Gas Well  Input Well  SWD Well  O&A

Other well as hereinafter indicated

Plugging Contractor Clarke Corporation License Number 5105

Address Box 187, Medicine Lodge, KS 67104

Company to plug at: Hour: 9 a.m. Day: 10 Month: 4 Year: 19 90

Plugging proposal received from Scott W. Scheuerman

(company name) Gore Oil Company (phone) 316-263-3535

were: 4 1/2" at 4839' PBD 4830' Perfs at 4746-4774'

1st plug sand back to 4700' with 4 sx cement on top of sand through bailer,

2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 1 sx hulls, 50 sx surefill and 50 sx 60/40 Pozmix 6% gel.

Plugging Proposal Received by Richard Lacey (TECHNICIAN)

Plugging Operations attended by Agent?: All  Part  None

Operations Completed: Hour: 11:50 a.m. Day: 10 Month: 4 Year: 19 90

ACTUAL PLUGGING REPORT 1st plug sanded back to 4700' and dumped 4 sx cement on top of sand through bailer,

2nd plug pumped 3 sx hulls, 10 sx gel, 50 sx 60/40 Pozmix 6% gel, 10 sx gel, 1 sx hulls, 50 sx surefill cement and 50 sx 60/40 Pozmix 6% gel.

Maximum pressure 300 psi and shut in 0 psi.

Remarks: Used 60/40 Pozmix 6% gel and surefill by B.J. Titan. Recovered 3800' of 4 1/2" casing. (if additional description is necessary, use BACK of this form.)

INVOICED observe this plugging.

DATE 4-24-90 4-18-90

INV. NO. 27943

Signed Richard W. Lacey (TECHNICIAN)