

1 040412

4-10

77R

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION 30' S SW SE NW SEC. 35, T 34 S, R 12 W/E
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 007-21,414-0000
2940 feet from S section line
3630 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5552

Lease Name Burgess B Well # 4

Operator: Gore Oil Company

County Barber 157.30

Name & Address 425 North Market, Suite 1750
202 So. St. Francis, Bx 2757

Well Total Depth 4840 feet

Wichita, KS 67202 67201-2757

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 817

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Clarke Corporation License Number 5105

Address Box 187, Medicine Lodge, KS 67104

Company to plug at: Hour: 3:45 p.m. Day: 10 Month: 4 Year: 19 90

Plugging proposal received from Scott Scheuerman

(company name) Gore Oil Company (phone) 316-263-3535

were: 4 1/2" at 4839' PBD 4829' Perfs at 4770-80' Elevation 1434' GL
1st plug sand back to 4720' and dump 4 sx cement on top of sand through bailer,
2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, 50 sx surefill
cement and 50 sx 60/40 Pozmix 6% gel cement.

Plugging Proposal Received by Richard Lacey
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 4:50 p.m. Day: 10 Month: 4 Year: 19 90

ACTUAL PLUGGING REPORT 1st plug sanded back to 4720' and dumped 4 sx cement on top
of sand through bailer,
2nd plug pumped down 8 5/8" surface pipe with 300 lbs. hulls, 10 sx gel, 50 sx 60/40
Pozmix 6% gel cement, 10 sx gel, 50 sx surefill cement and 50 sx 60/40 Pozmix 6% gel
cement. Left out last 100# hulls due to high pumping pressure.
Maximum pressure 1000 psi and shut in 400 psi.

Remarks: Used 60/40 Pozmix 6% gel and surefill cement by B.J. Services. Recovered 3200' of
(If additional description is necessary, use BACK of this form.) 4 1/2" casing.

Observe this plugging.

Signed Stephen J. Pfeifer
(TECHNICIAN)

RECEIVED
STATE CORPORATION COMMISSION
4-12-90
INVOICED
APR 12 1990

DATE CONSERVATION DIVISION
Wichita, Kansas 4-24-90

INV. NO. 27941