

To: 1 040416
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

4-17 1962
API NUMBER 15-007-21,864-0000
SE NE NE, SEC. 35, T 34 S, R 12 W/E
4290 feet from S section line
330 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5552

Lease Name Morton "B" Well # 4

Operator: Gore Oil Company

County Barber 157.63

Name & Address 125 North Market, Suite 1750

Well Total Depth 4850 feet

Wichita, KS 67202

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 803

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Clarke Corporation License Number 5105

Address Box 187, Medicine Lodge, KS 67104

Company to plug at: Hour: 12:15 p.m. Day: 17 Month: 4 Year: 19 90

Plugging proposal received from Scott Scheuerman

(company name) Gore Oil Company (phone) 316-263-3535

logs: 4 1/2" at 4849' PBD 4839' Perfs at 4752-68'

1st plug sand back to 4700' and dump 4 sx cement on top of sand through bailer,

2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls and 50 sx

surefill cement, and 50 sx 60/40 Pozmix 6% gel.:

Plugging Proposal Received by Steve Pfeifer
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 1 p.m. Day: 17 Month: 4 Year: 19 90

ACTUAL PLUGGING REPORT 1st plug sanded back to 4700' and dumped 4 sx cement on top of sand through bailer,

2nd plug pumped down 8 5/8" surface pipe with 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, 50 sx surefill cement, and 50 sx 60/40 Pozmix 6% gel.

Maximum pressure 1000 psi and shut in 800 psi.

Remarks: Used 60/40 Pozmix 6% gel and surefill cement by B.J. Services. Rec' 3480'
(If additional description is necessary, use BACK of this form.)

INVOICED

DATE 5-3-90

WV. NO. 28079

APR 30 1990
4-30-90
CONSERVATION
Wichita, Kansas

Signed Stephen J. Pfeifer
(TECHNICIAN)