

To: 1 040418
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

4-17 194
API NUMBER 15- 007-21,701-0000
NW NE NE, SEC. 35, T 34 S, R 12 W/E

TECHNICIAN'S PLUGGING REPORT
Operator License # 5552
Operator: Gore Oil Company
Name & Address 125 North Market, Suite 1750
Wichita, KS 67202

4950 feet from S section line
990 feet from E section line
Lease Name Morton "B" Well # 2
County Barber 157.56
Well Total Depth 4848 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 331

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____
Other well as hereinafter indicated _____

Plugging Contractor Clarke Corporation License Number 5105
Address Box 187, Medicine Lodge, KS 67104

Company to plug at: Hour: 10:30 a.m. Day: 17 Month: 4 Year: 19 90

Plugging proposal received from Scott Scheuerman
(company name) Gore Oil Company (phone) 316-263-3535

were: 4 1/2" at 4847' PBD 4831' Perfs at 4760-84'
1st plug sand back to 4700' and dump 4 sx cement on top of sand through bailer,
2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, 50 sx surefill
cement, and 50 sx 60/40 Pozmix 6% gel.

Plugging Proposal Received by Steve Pfeifer
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 11:15 a.m. Day: 17 Month: 4 Year: 19 90

ACTUAL PLUGGING REPORT 1st plug sanded back to 4700' and dumped 4 sx cement on top of
sand bridge through bailer,

2nd plug pumped down 8 5/8" surface pipe with 300 lbs. hulls, 10 sx gel, 50 sx 60/40
Pozmix 6% gel cement, 10 sx gel, 100 lbs. hulls, 50 sx surefill cement, and 50 sx
60/40 Pozmix 6% gel cement.

Maximum pressure 300 psi and shut in 0 psi. Well on vacuum.

Remarks: Used 60/40 Pozmix 6% gel and surefill cement by B.J. Services. Recovered 3780' of
(if additional description is necessary, use BACK of this form.) 4 1/2" casing.

INVOICED
DATE 5-3-90
INV. NO. 28022

APR 30 1990
4-30-90
CONSERVATION
Wichita, Kansas

Signed Steve Pfeifer
(TECHNICIAN)