

To: 1 041265 9-12
STATE CORPORATION COMMISSION
Wichita State Office Bldg. - PLUGGING SECTION
130 S. Market, Room 2078
Wichita, KS 67202

API NUMBER 15- 007-20,952
NE SE SE, SEC. 35, T 34 S, R 12 W/E
990 feet from S section line
330 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License / 6006
Operator: Molz Oil Company
Name:
Address RR 2, Box 54
Kiowa, KS 67070-0054

Lease Name Norma (Short) Well # 1
County Barber 158.28
Well Total Depth 4870 feet
Conductor Pipe: Size feet
Surface Casing: Size 8 5/8 feet 381

Abandoned Oil Well Gas Well Input Well SWD Well O&A
Other well as hereinafter indicated

Plugging Contractor Clarke Corporation License Number 5105
Address P.O. Box 187, Medicine Lodge, KS

Company to plug at: Hour: 11 a.m. Day: 12 Month: 9 Year: 1997

Plugging proposal received from Alan Vratil
(company name) Clarke Corporation (phone) 316-886-5665

Work: 4 1/2" at 4869' w/150 sx cement, PBSD 4859', Perfs at 4804-21'
1st plug sand back to 4750' and dump 4 sx cement on top of sand through bailer,
2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8"
wiper plug and pump 100 sx cement.

RECEIVED
KANSAS CORPORATION COMMISSION
SEP 17 1997
STEVE PFEIFER
(TECHNICIAN)
CONSTRUCTION DIVISION
WICHITA, KS

Plugging Proposal Received by Steve Pfeifer

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 11:30 a.m. Day: 12 Month: 9 Year: 1997

ACTUAL PLUGGING REPORT 1st plug sanded back to 4700' and dumped 4 sx cement on top of sand bridge through bailer,

2nd plug pumped down 8 5/8" surface pipe with 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, released 8 5/8" wiper plug and pumped 100 sx cement.
Maximum pressure 400 psi and shut in 200 psi.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 3700' of 4 1/2" casing.
(If additional description is necessary, use BACK of this form.)

INVOICED
Reserve this plugging.

DATE 9-23-97
INV. NO. 49086

Signed Steve Pfeifer (TECHNICIAN)