

4-10 113 R
API NUMBER 15- 007-21,378-00-01

To: 1 051289
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

SW SW NW, SEC. 35, T 34 S, R 12 W/E
2970 feet from S section line
4950 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5552

Lease Name Burgess "B" Well # 1

Operator: Gore Oil Company

County Barber 157.27

Name & Address 125 North Market, Suite 1750

Well Total Depth 4839 feet

202 So. St. Francis
Wichita, KS 67202 Suite 2757
67201-2757

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 340

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Clarke Corporation License Number 5105

Address Box 187, Medicine Lodge, KS 67104

Company to plug at: Hour: 12 p.m. Day: 10 Month: 4 Year: 19 90

Plugging proposal received from Scott W. Scheuerman

(company name) Gore Oil Company (phone) 316-263-3535

were: 4 1/2" at 4838' PRTD 4828' Perfs at 4778-86' Elevation 1433' KB.

1st plug sand back to 4725' and dump 4 sx cement on top of sand through bailer,

2nd plug pump 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, 50

sx surefill and 50 sx 60/40 Pozmix 6% gel.

Plugging Proposal Received by Richard Lacey (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 1:10 p.m. Day: 10 Month: 4 Year: 19 90

ACTUAL PLUGGING REPORT 1st plug sanded back to 4720' and dumped 4 sx cement on top of sand through bailer,

2nd plug pumped 3 sx hulls, 10 sx gel, 50 sx 60/40 Pozmix 6% gel, 10 sx gel, 1 sx hulls, 50 sx surefill cement and 50 sx 60/40 Pozmix 6% gel.

Maximum pressure 300 psi and shut in 200 psi.

Remarks: Used 60/40 Pozmix 6% gel and surefill by B.J. Titan. Recovered 3850' of 4 1/2" casing.

(If additional description is necessary, use BACK of this form.)

INVOICED (If you wish to observe this plugging.)

DATE 4-24-90 4-18-90
INV. NO. 27944
APR 18 1990
WICHITA, KANSAS

Signed Richard W. Lacey (TECHNICIAN)