

3-30-88

To: 1 040075
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 007-21,237 - 0000
SW NW SW, SEC. 35, T 34 S, R 12 W/E
1650 feet from S section line
4950 feet from E section line

TECHNICIAN'S PLUGGING REPORT
Operator License # 5042
Operator: Edmiston Oil Company, Inc.
Name & Address: 1260 Kansas State Bank Bldg.
Wichita, KS 67202

Lease Name Morton "A" Well # 4
County Barber 156.81
Well Total Depth 4825 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 10 3/4 feet 327

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pulling License Number 6050
Address P.O. Box 347, Chase, KS 67524

Company to plug at: Hour: 4 p.m. Day: 30 Month: 3 Year: 1988

Plugging proposal received from Millard Kelso
(company name) Kelso Casing Pulling (phone) 316-938-2457

were: 4 1/2" at 4824' Perfs at 4750-60, 4770-84'
1st plug sand back to 4700' and dump 4 sx cement on top of sand through bailer,
2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, release 10 3/4" wiper plug
and pump 100 sx cement.

Plugging Proposal Received by Steve Durrant (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 4:45 p.m. Day: 30 Month: 3 Year: 1988

ACTUAL PLUGGING REPORT 1st plug sanded back to 4700' and dumped 4 sx cement on top of sand through bailer,

2nd plug pumped down 10 3/4" surface pipe with 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, and 150 sx cement.

RECEIVED
STATE CORPORATION COMMISSION

Maximum pressure 450 psi and shut in 300 psi. APR 11 1988
4-11-88

Remarks: Used 60/40 Pozmix 6% gel by B.J. Titan. Recovered 3505' of 4 1/2" casing. (If additional description is necessary, use BACK of this form.)

INVOICED

DATE 4-13-88
INV. NO. 20344

(If desired, observe this plugging.)

Signed Stephen J. Pfeifer (TECHNICIAN)