

11-20

1 040358

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-007-21,236-0000  
SW SW SW, SEC. 35, T 34 S, R 12 W/E  
330 feet from S section line  
4950 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5552  
Operator: Gore Oil Company  
Name & Address 125 North Market, Suite 1750  
Wichita, KS 67202

Lease Name Morton "A" Well # 3  
County Barber 157.63  
Well Total Depth 4850 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 10 3/4 feet 310

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_  
Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Clarke Corporation License Number 5105  
Address P.O. Box 187, Medicine Lodge, KS 67104

Company to plug at: Hour: 12:30 p.m. Day: 20 Month: 11 Year: 19 89

Plugging proposal received from Scott Scheuerman  
(company name) Gore Oil Company (phone) 316-263-3535  
were: 4 1/2" at 4849' PBD 4832' Perfs at 4788-92'

1st plug sand back to 4730' and dump 4 sx cement on top of sand through bailer,  
2nd plug pump 4 sx hulls, 10 sx gel, 50 sx cement 10 sx gel, 1 sx hulls, release 10 3/4" wiper plug and pump 100 sx cement.

Plugging Proposal Received by Steve Pfeifer  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 1:00 p.m. Day: 20 Month: 11 Year: 19 89

ACTUAL PLUGGING REPORT 1st plug sanded back to 4730' and dumped 4 sx cement on top of sand bridge with bailer,  
2nd plug pumped down 10 3/4" surface pipe with 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, released 10 3/4" wiper plug and pumped 130 sx cement.  
Maximum pressure 400 psi and shut in 300 psi.

RECEIVED  
STATE CORPORATION COMMISSION  
NOV 28 1989

Remarks: Used 60/40 Pozmix 6% gel by B.J. Titan. Recovered 3550' of 4 1/2" casing.  
(If additional description is necessary, use BACK of this form.)

**INVOICED**

DATE 12-6-89  
INV. NO. 26639

Signed Stephen J. Pfeifer  
(TECHNICIAN)