

5-10-88

1 040097

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 007-21,293-0000  
SW SW NE, SEC. 35, T 34 S, R 12 W/EX  
2970 feet from S section line  
2310 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5042  
Operator: Edmiston Oil Company, Inc.  
Name & Address 1260 Kansas State Bank Bldg.  
Wichita, KS 67202

Lease Name Morton "B" Well # 1  
County Barber 157.63  
Well Total Depth 4850 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 feet 321

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Kelso Casing Pulling License Number 6050  
Address Box 347, Chase, KS 67524

Company to plug at: Hour: 1 p.m. Day: 10 Month: 5 Year: 19 88

Plugging proposal received from Millard Kelso  
(company name) Kelso Casing Pulling (phone) 316-938-2457  
were: 4 1/2" at 4844' PBD 4845' Perfs at 4790-96'

1st plug sand back to 4740' and dump 4 sx cement on top of sand through bailer,  
2nd plug pump 4 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8"  
wiper plug and pump 130 sx cement.

Plugging Proposal Received by Paul A. Luthi  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 1:45 p.m. Day: 10 Month: 5 Year: 19 88

ACTUAL PLUGGING REPORT 1st plug sanded back to 4740' and dumped 4 sx cement on top of  
sand through bailer,  
2nd plug pumped down 8 5/8" with 400 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs.  
hulls, released 8 5/8" wiper plug and pumped 100 sx cement.

RECEIVED  
STATE CORPORATION COMMISSION

Maximum pressure 500 psi and shut in 300 psi.

MAY 13 1988

Remarks: Used 60/40 Pozmix 6% gel by B.J. Titan. Recovered 3570' of 4 1/2" casing.  
(If additional description is necessary, use BACK of this form.)

5-13-88  
CONSERVATION DIVISION  
Wichita, Kansas

INVOICED

(operator / technician) observe this plugging.

Signed Stephen J. Pfeifer  
(TECHNICIAN)

DATE 5-17-88

INV. NO. 20632