

To: 1 040411
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

4-10 15-007-21379-9009
API NUMBER 15- Docket #D-21,120

TECHNICIAN'S PLUGGING REPORT

SW NW NW, SEC. 35, T 34 S, R 12 W/E
4290 feet from S section line
4950 feet from E section line

Operator License # 5552

Lease Name Burgess Well # B-2

Operator: Gore Oil Company
Name & Address 125 North Market, Suite 1750
Wichita, KS 67202

County Barber 156.98

Well Total Depth 4830 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 317

Abandoned Oil Well Gas Well _____ Input Well _____ SMD Well D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Clarke Corporation License Number 5105

Address Box 187, Medicine Lodge, KS 67104

Company to plug at: Hour: 2:15 p.m. Day: 10 Month: 4 Year: 19 90

Plugging proposal received from Scott Scheuerman

(company name) Gore Oil Company (phone) 316-263-3535

were: 4 1/2" at 4829' PBSD 4700' Perfs at 4392-4400'

1st plug sand back to 4330' and dump 4 sx cement on top of sand through bailer,

2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, 50 sx surefill cement and 50 sx 60/40 Poz, 6% gel cement.

Plugging Proposal Received by Richard Lacey
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 3 p.m. Day: 10 Month: 4 Year: 19 90

ACTUAL PLUGGING REPORT 1st plug sanded back to 4330' and dumped 4 sx cement on top of sand through bailer.

2nd plug pumped down 8 5/8" surface pipe with 300 lbs. hulls, 10 sx gel, 50 sx 60/40 Pozmix 6% gel cement, 10 sx gel, 100 lbs. hulls, 50 sx surefill cement, 50 sx 60/40 Pozmix 6% gel cement.

Maximum pressure 300 psi and shut in 200 psi.

Remarks: Used 60/40 Pozmix 6% gel & surefill cement by B.J. Services. Recovered 3040' of 4 1/2" casing.
(If additional description is necessary, use BACK of this form.)

INVOICED
Wichita, Kansas
observe this plugging.

Signed Stephen J. Pifer
(TECHNICIAN)

DATE 4-24-90

INV. NO. 27942