

2010076

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 077 2c 967-00-00

SWSE, SEC. 3, T 32 S, R 6

660 feet from section line

660 feet from section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5087

Lease Name HOSTETLER Well # 1-3

Operator: TEXAS ENERGIES

County HARPER

Name: Address Box 947

Well Total Depth 4380 142.35 feet

PRATT, KS

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 258

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor GABBERT & JONES License Number 3842

Address WICHITA, KS

Company to plug at: Hour: 4:00 AM Day: 18 Month: 4 Year: 1984

Plugging proposal received from

(company name) (phone)

were:

Plugging Proposal Received by RALPH TITTE (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 7:00 AM Day: 18 Month: 4 Year: 1984

ACTUAL PLUGGING REPORT RUN DRILL PIPE TO 1,200' HOW CO. SPOTTED 35 SKS

CEMENT, FILLED HOLE WITH 10 BARREL 36 VIS. MUD. PULLED DRILL

PIPE TO 330' SPOTTED 35 SKS CEMENT, PULLED DRILL PIPE TO 60'

SPOTTED 25 SKS CEMENT, RUN ONE (1) JOINT OF DRILL PIPE IN

BAT HOLE SPOTTED 10 SKS CEMENT, SPOTTED 10 SKS CEMENT IN

WATER WELL.

Remarks:

(If additional description necessary, use BACK of this form.)

INVOICED

DATE 5-2-84

INV. NO. 1339

STATE CORPORATION COMMISSION RECEIVED APR 30 1984 CONSERVATION DIVISION Wichita, Kansas

Signed W. K. Kubit (TECHNICIAN)

4-18

PLUGGING SUMMARY

Date 4-18-84 Time 7:25 PM API Number 15-077-20967

Who Called DEAN C-SW-SE, Sec. 3, T 32 S, R 6

Phone No. _____ 660 feet from section line

Directions 3/4 E. HARPER 660 feet from section line

Lease Name HOSTETLER Well# 1-3

Operator: TEXAS ENERGIES Lic# 5087 County HARPER

Address Box 947 Conductor Pipe: Size _____ Feet _____

PRATT, KS Surface Casing: Size 8 5/8 Feet 258

Well TD 4380 ft. TD formation MISS

Production Pipe: Size _____ Feet _____ Cement _____

Elevation _____ Anhydrite 1280 Salt Member _____

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A

Plugging Contractor GABBERT & JONES Lic # 5842 Tag# 386

Address _____ WICHITA, KS

Company to plug at: Hour 4:00 AM Day: 18 Month: 4 Year: 19 84

Current Operations DRILLING

Perforations _____ P.B.T.D. _____ Perfs _____

Condition of well: _____ Bad Pipe _____ Bridged _____

Tubing in hole/pipe _____ Packer @ _____

Gas Zone _____ Hole taking/making fluid _____ Depth _____

Mud wt 10 Viscosity 37

Operations completed: Hour 7:00 AM Day 18 Month 4 Year 19 84

VERBAL PLUGGING RECOMMENDATIONS 35 SKS 1200' 35 SKS 330' 25 SKS 60'

10 SKS RAT HOLE 10 SKS WELL WELL

RECEIVED
STATE CORPORATION COMMISSION

Actual _____

APR 30 1984

CONSERVATION DIVISION
Wichita, Kansas

Cement Company Howco Ticket # 883385