

1 030793

APR 29 1987

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-175-20,944 7000
C W/2 NE, SEC. 11, T 33 S, R 32 W/R X
3960 feet from S section line
1980 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5263
Operator: Midwestern Exploration Company
Name &
Address 111 East 11th
Liberal, KS 67901

Lease Name McVey Well # 1-11
County Seward 202.80
Well Total Depth 6240 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 1585

Abandoned Oil Well _____ Gas Well X Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Sargent's Casing Pulling Service License Number 6547
Address Box 506, Liberal, KS 67901

Company to plug at: Hour: 12 p.m. Day: 29 Month: 4 Year: 19 87

Plugging proposal received from Kirby Lillard
(company name) Sargent's Casing Pulling Service (phone) 316-624-7455

were: 4 1/2" at 5895' PBD 5845' Perfs at 5756-5772'

1st plug pump down chase with water 1sx hulls and 20 sx cement - stop plug at 5500',

2nd plug at 1600' with 40 sx cement,

3rd plug at 700-600' with 35 sx cement,

4th plug at 0-40' with 10 sx cement.

Plugging Proposal Received by Don Ubel
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None X

Operations Completed: Hour: 5 p.m. Day: 29 Month: 4 Year: 19 87

ACTUAL PLUGGING REPORT 1st plug pumped down-chase with water - 1 sx hulls and 20 sx
cement - stopped plug at 5500',

2nd plug pump 40 sx cement at 1600',

3rd plug pump 35 sx cement at 700-600',

4th plug pump 10 sx cement at 0-40'.

RECEIVED
STATE CORPORATION COMMISSION
MAY 4 1987

Remarks: Recovered 4832' of 4 1/2" casing. Used common cement by Sargent's.
(If additional description is necessary, use BACK of this form.)

INVOICED
observe this plugging.

Signed Steve Purson
(TECHNICIAN) DP

DATE 5-5-87

INV. NO. 16765