

1 030760

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-025-20,970 0000

SW SE SE, SEC. 33, T 32 S, R 21 W/E
330 feet from S section line
990 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5254

Lease Name Wilson Well # 1

Operator: Midco Exploration, Inc.
Name & Address: 200 East 1st, Suite 411
Wichita, KS 67202

County Clark 176.31

Well Total Depth 5425 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 636

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X

Other well as hereinafter indicated _____

Plugging Contractor Murfin Drilling Company License Number 6033

Address 250 North Water, Suite 300, Wichita, KS 67202

Company to plug at: Hour: 11 a.m. Day: 9 Month: 12 Year: 19 86

Plugging proposal received from Terry McRae

(company name) Murfin Drilling Company (phone) 913-743-2559

were: to fill hole with heavy mud and spot cement through drill pipe Elevation 1963'
Anhydrite 960-990'

1st plug at Base Anhydrite with 50 sx cement,

2nd plug at 660' with 50 sx cement, 3rd plug at 40' with 10 sx cement,

4th plug to circulate rathole with 10 sx cement,

5th plug to circulate mousehole with 10 sx cement.

Plugging Proposal Received by Steve Durrant
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None X

Operations Completed: Hour: 1:30 p.m. Day: 9 Month: 12 Year: 19 86

ACTUAL PLUGGING REPORT 1st plug at 1780' with 50 sx cement,

2nd plug at 660' with 50 sx cement,

3rd plug at 40-0' with 10 sx cement,

4th plug to circulate rathole with 10 sx cement,

5th plug to circulate mousehole with 10 sx cement.

STATE CORPORATION COMMISSION

DEC 12 1986

Remarks: Used 60/40 Pozmix 6% gel by Halliburton.
Wichita, Kansas

(If additional description is necessary, use BACK of this form.)

INVOICED

DATE 12-12-86

Signed Steve Durrant
(TECHNICIAN)

REV. NO. 15615
12-9 JAN 0 8 1987

NOTICE OF INTENTION TO DRILL

(see rules on reverse side)

Starting Date 11 23 86 month day year

API Number 15- 025-20,970

OPERATOR: License # 5254 Name MIDCO EXPLORATION, INC. Address 200 East 1st, Suite 411 City/State/Zip Wichita, Kansas 67202 Contact Person Harvey Gough Phone 316/267-3613

SW. SE. SE Sec. 33 Twp. 32 S, Rg. 21 X West 330 Ft. from South Line of Section 990 Ft. from East Line of Section

CONTRACTOR: License # 6033 Name Murfin Drilling Company City/State Wichita, Kansas 67202

(Note: Locate well on Section Plat on reverse side) Nearest lease or unit boundary line 330 feet County Clark

Well Drilled For: X Oil SWD Infield Mud Rotary Gas Inj Pool Ext Air Rotary OWWO Expl Wildcat Cable

Lease Name Wilson Well # 1 Ground surface elevation Unknown feet MSL Domestic well within 330 feet: yes X no Municipal well within one mile: yes X no Depth to bottom of fresh water 120 Depth to bottom of usable water 200 Surface pipe by Alternate: 1 X 2

If OWWO: old well info as follows: Operator Well Name Comp Date Old Total Depth

Surface pipe planned to be set 500 Conductor pipe required 60 Projected Total Depth 5375 feet Formation Mississippi

I certify that well will comply with K.S.A. 55-101, et seq., plus eventually plugging hole to KCC specifications. Date 11-13-86 Signature of Operator or Agent Harvey Gough Title Vice President

For KCC Use: Conductor Pipe Required feet; Minimum Surface Pipe Required 200 feet per Alt. This Authorization Expires 5-20-87 Approved By 11-20-86

Cond. BS 20" 898 636

REH/KR

PLUGGING PROPOSAL IF ABOVE IS D & A

This plugging proposal will be reviewed and approved or revised at the time the district office is called prior to setting surface casing (call 7 a.m. to 5 p.m. workdays).

1st plug @ 1780 B Any feet depth with 50 sxs of Cement 2nd plug @ 840-660 feet depth with 50 sxs of 3rd plug @ Bottom of Surface Pipe feet depth with 50 sxs of 4th plug @ 40 feet depth with 10 sxs of 5th plug @ feet depth with sxs of (2) Rathole with 15 10 sxs (b) Mousehole with 10 sxs

PUSHER Terry McCreary TD 5425 FORMATION MISS SURFACE PIPE 8 3/8 @ 636 ANHYDRITE 970 B ELEVATION 1963 12-9-86 STARTING TIME & DATE 11:00 AM COMPLETION TIME & DATE 1:30 PM 1st PLUG @ 1780 FT. W/ 50 SX 2nd PLUG @ 660 FT. W/ 50 SX 3rd PLUG @ 40-0 FT. W/ 10 SX 4th PLUG @ FT. W/ SX RAT HOLE CIRCULATED W/ 10 SX MOUSE HOLE CIRCULATED W/ 10 SX WATER WELL PLUGGED W/ 260 CEMENT COMPANY Haliburton TECHNICIAN Steve Durrant 60/40 pps w/ 6 3/8 gel

STATE CORPORATION COMMISSION DEC 12 1986 CONSERVATION DIVISION Wichita, Kansas