

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-065-01570-00-00
Spot: SWSWSW Sec/Twnshp/Rge: 31-9S-23W
330 feet from S Section Line, 4950 feet from E Section Line
Lease Name: HOOF NW LKC UNIT Well #: 108W
County: GRAHAM Total Vertical Depth: 3981 feet

Operator License No.: 30606
Op Name: MURFIN DRILLING CO., INC.
Address: 250 N WATER STE 300
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	3981		125 sx
SURF	8.625	189		150 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 11/26/2013 10:00 AM
Plug Co. License No.: 30606 Plug Co. Name: MURFIN DRILLING CO., INC.
Proposal Rcvd. from: JOHN GERSTNER Company: MURFIN DRILLING CO., INC. Phone: (316) 267-3241

Proposed Plugging Method: Ordered 437 sx 60/40 pozmix 4% gel cement and 700 # hulls.

Plugging Proposal Received By: RICHARD WILLIAMS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 11/27/2013 10:00 AM KCC Agent: TOM CULLEY

Actual Plugging Report:

Ran tubing to 3706' and pumped 125 sx cement w/300 # hulls. Pulled tubing to 2090' and pumped 150 sx cement w/200 # hulls. Cement did not circulate. Pulled tubing to 1250' and waited one hour. Pumped 125 sx cement w/200 # hulls. No circulation of cement.
11/27/2013- Tagged cement w/tubing at 346'. Pulled one joint to 316' and pumped 27 sx cement to circulate cement to surface. Pulled tubing out of hole and pressured 8 5/8" surface casing to 200 psi w/10 sx cement. Filled 4 1/2" production casing.

GPS: 39.22006 -099.93964

Perfs:


Top	Bot	Thru	Comments
3963	3967		
3946	3949		
3864	3866		

Remarks: SWIFT SERVICES TICKET # 25245

Plugged through: TBG

District: 04

Signed


01/17/14 (TECHNICIAN)
KCC WICHITA

CM

DEC 19 2013

Form CP-2/3

DEC 05 2013

RECEIVED