

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-171-20254-00-00
Spot: NESWNWSE Sec/Twnshp/Rge: 26-19S-33W
1817 feet from S Section Line, 2000 feet from E Section Line
Lease Name: SMITH Well #: 15
County: SCOTT Total Vertical Depth: 4870 feet

Operator License No.: 31714
Op Name: NOVY OIL & GAS, INC.
Address: PO BOX 559
GODDARD, KS 67052

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		4050		WITH 2 SX CMT
DVT		2185		WITH 500 SX CMT
PROD	5.5	4860	0	WITH 800 SX CMT
SURF	8.625	364		WITH 270 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 12/20/2013 9:30 AM
Plug Co. License No.: 32382 Plug Co. Name: SWIFT SERVICES, INC.
Proposal Rcvd. from: KIRK GLENN Company: NOVY OIL & GAS Phone: (620) 282-2212

Proposed Plugging Method: CIBP @ 4050' WITH 2 SX CMT. RUN TBG TO 2170' & CIRCULATE CMT. PRESSURE TEST 8 5/8" X 5 1/2" ANNULUS TO 500 PSIG WITH CMT.

Plugging Proposal Received By: RICHARD LACEY Witness Type: NONE
Date/Time Plugging Completed: 12/20/2013 11:30 AM KCC Agent: RICHARD LACEY

Actual Plugging Report:

CIBP @ 4050' WITH 2 SX CMT. RAN TBG TO 2220'. CIRCULATED CMT WITH 225 SX. TRIPPED OUT TBG & TOPPED OFF WITH 25 SX CMT. PRESSURE BACKSIDE TO 500 PSIG. 10 SX CMT USED.

Perfs:

Top	Bot	Thru	Comments
4796	4799		
4714	4717		
4088	4099		
4050			

Remarks: USED 60/40 POZMIX 4% GEL BY SWIFT SERVICES.

Plugged through: TBG

KCC WICHITA

JAN 07 2014

RECEIVED

District: 01

Signed Richard M. Lacey
01/17/14 (TECHNICIAN)

RECEIVED

DEC 31 2013

KCC DODGE CITY