

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-051-02750-00-00
Spot: NWSENWSW Sec/Twnshp/Rge: 26-13S-17W
1653 feet from S Section Line, 4411 feet from E Section Line
Lease Name: BRAUN B Well #: 2
County: ELLIS Total Vertical Depth: 3523 feet

Operator License No.: 8061
Op Name: OIL PRODUCERS INC. OF KANSAS
Address: 1710 WATERFRONT PKWY
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3512		75 SX
SURF	8.625	323		200 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 12/30/2013 11:00 AM
Plug Co. License No.: 34082 Plug Co. Name: ALLIANCE WELL SERVICE INC.
Proposal Rcvd. from: BERRY WALTERS Company: ALLIANCE WELL SERVICE INC. Phone: (620) 655-4494

Proposed	Ordered 450 sx 60/40 pozmix 4% gel cement and 500 # hulls.
Plugging	Bad Casing. Squeezed- 1956' - 633' w/200 sx cement. Squeezed 1958' - 879' w/150 sx cement.
Method:	Perforations: 3512' - 3522 ARB. PBTB- 3522'

Plugging Proposal Received By: PAT STAAB WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 12/30/2013 3:15 PM KCC Agent: PAT STAAB

Actual Plugging Report:

Gemini Wireline Services perforated at 1650, 1182' and 650'. Alliance ran in hole with tubing to 3295'. Allied rigged to tubing and mixed and pumped 165 sx cement w/300 # hulls mixed in. Pulled tubing to 1650'. Allied rigged to tubing and mixed and pumped 120 sx cement w/200 # hulls mixed in to circulate cement to surface up 5 1/2" casing and pumped 25 sx cement to pressure with 200 psi and 200 psi shut in pressure. 8 5/8" casing full of cement per visual check.

GPS: 38.89044 -099.18447
1667' FSL 4321' DEL
NW SE NW SW

Perfs:

Top	Bot	Thru	Comments
3512	3522		

KCC WICHITA

Remarks: ALLIED CEMENTING CO TICKET # 54956


JAN 06 2014

Plugged through: TBG

RECEIVED

District: 04

Signed


01/17/14 (TECHNICIAN)

CM

DEC 31 2013