

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-135-25359-00-00
Spot: NWSENESE Sec/Twnshp/Rge: 20-19S-24W
1664 feet from S Section Line, 359 feet from E Section Line
Lease Name: BILL MELLIES Well #: 1
County: NESS Total Vertical Depth: 4417 feet

Operator License No.: 30742
Op Name: PALOMINO PETROLEUM, INC.
Address: 4924 SE 84TH ST
NEWTON, KS 67114

String	Size	Depth (ft)	Pulled (ft)	Comments
PC		1552		
PROD	5.5	4416	0	WITH 145 SX CMT
SURF	8.625	814		WITH 400 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 12/18/2013 8:00 AM
Plug Co. License No.: 32382 Plug Co. Name: SWIFT SERVICES, INC.
Proposal Revd. from: GLEN DINKEL Company: PALOMINO PETROLEUM Phone: (785) 735-8199

Proposed Plugging Method: PUMP 40 SX CMT & 200# HULLS. OPEN PORT COLLAR & CIRCULATE 380 SX CMT TO SURFACE.

Plugging Proposal Received By: MICHAEL MAIER Witness Type: NONE
Date/Time Plugging Completed: 12/18/2013 1:30 PM KCC Agent: MICHAEL MAIER

Actual Plugging Report:

PUMP 40 SX CMT & 200# HULLS. RUN TBG TO PORT COLLAR @ 1552' & OPEN.
PUMPED 60 BBL MUD THEN 380 SX CMT. CMT CIRCULATED.

Perfs:

Top	Bot	Thru	Comments
4374	4376		
4367	4370		

Remarks: USED 60/40 POZMIX 4% GEL BY SWIFT SERVICES.

Plugged through: TBG

KCC WICHITA

DEC 20 2013

RECEIVED

District: 01

Signed

Michael Maier
02/17/14

(TECHNICIAN)

RECEIVED

DEC 19 2013

KCC DODGE CITY