

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-171-21011-00-00
Spot: SWSESWE Sec/Twnshp/Rge: 1-17S-34W
100 feet from S Section Line, 1870 feet from E Section Line
Lease Name: JANZEN Well #: 1-1
County: SCOTT Total Vertical Depth: 4902 feet

Operator License No.: 6113
Op Name: LANDMARK RESOURCES, INC.
Address: 1616 S VOSS RD STE 600
HOUSTON, TX 77057

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	261		210 SX CEMENT

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 12/22/2013 10:00 PM
Plug Co. License No.: 30606 Plug Co. Name: MURFIN DRILLING CO., INC.
Proposal Revd. from: KELLY WILSON Company: MURFIN DRILLING CO., INC. Phone: (316) 267-3241

Proposed Plugging Method: 1ST PLUG AT 2430' WITH 50 SX CMT. 2ND PLUG AT 1550' WITH 80 SX CMT. 3RD PLUG AT 775' WITH 50 SX CMT. 4TH PLUG AT 300' WITH 50 SX CMT. 5TH PLUG AT 60' WITH 20 SX CMT. 6TH PLUG TO CIRCULATE RAT HOLE WITH 30 SX CMT. 7TH PLUG TO CIRCULATE MOUSE HOLE WITH 20 SX CMT.

Plugging Proposal Received By: NATHAN WILLIS WitnessType: NONE
Date/Time Plugging Completed: 12/23/2013 1:00 AM KCC Agent: NATHAN WILLIS

Actual Plugging Report:

Perfs:

1ST PLUG AT 2430' WITH 50 SX CMT. 2ND PLUG AT 1550' WITH 80 SX CMT. 3RD PLUG AT 775' WITH 50 SX CMT. 4TH PLUG AT 300' WITH 50 SX CMT. 5TH PLUG AT 60' WITH 20 SX CMT. 6TH PLUG TO CIRCULATE RAT HOLE WITH 30 SX CMT. 7TH PLUG TO CIRCULATE MOUSE HOLE WITH 20 SX CMT.

Remarks: USED 60/40 POZMIX 4% GEL 1/4# FLO SEAL BY ALLIED.

Plugged through: DP

KCC WICHITA

JAN 07 2014

RECEIVED

District: 01

RECEIVED

DEC 31 2013

KCC DODGE CITY

Signed

Nathan Willis
12/17/14

(TECHNICIAN)