

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-185-21138-00-00  
Spot: SESWSW Sec/Twnshp/Rge: 29-22S-11W  
290 feet from S Section Line, 984 feet from W Section Line  
Lease Name: P SPANGENBERG Well #: 8  
County: STAFFORD Total Vertical Depth: 3577 feet

Operator License No.: 32432  
Op Name: LA VETA OIL & GAS, LLC  
Address: 312 N BUFFALO  
STAFFORD, KS 67578

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		3000		WITH 2 SX CMT
CIBP		3500		
PROD	5.5	3571	901	WITH 215 SX CMT
SURF	8.625	556		WITH 300 SX CMT

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 12/27/2013 10:00 AM  
Plug Co. License No.: 7023 Plug Co. Name: KLIMA WELL SERVICE, INC.  
Proposal Rcvd. from: MARTY ZIEGLER Company: LAVETA OIL & GAS Phone: (620) 546-4559

Proposed Plugging Method: SET CIBP @ 3000' WITH 2 SX CMT. PLUG AT 600' WITH 12 SX GEL & 50 SX CMT. PLUG AT 300' WITH 40 SX CMT. PLUG AT 40' WITH 20 SX CMT.

Plugging Proposal Received By: RICHARD LACEY Witness Type: PARTIAL  
Date/Time Plugging Completed: 12/27/2013 11:30 AM KCC Agent: MICHAEL MAIER

Actual Plugging Report:

SET CIBP @ 3000' WITH 2 SX CMT. 1ST PLUG AT 588' WITH 12 SX GEL & 50 SX CMT. 2ND PLUG AT 298' WITH 40 SX CMT. 3RD PLUG AT 44' WITH 20 SX CMT.

Perfs:

Top	Bot	Thru	Comments
3410	3416		
3318	3328		

Remarks: \*\*COMPLIANCE ISSUE: DENIED TA SI 10 YRS\*\* USED 60/40 POZMIX 4% GEL BY ALLIED.  
Plugged through: CSG

KCC WICHITA  
JAN 07 2014  
RECEIVED

District: 01

RECEIVED  
DEC 31 2013  
KCC DODGE CITY

Signed Michael Maier  
01/17/14 (TECHNICIAN)