

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-035-23208-00-01  
Spot: SWNESWNE Sec/Twnshp/Rge: 21-32S-4E  
3597 feet from S Section Line, 1682 feet from E Section Line  
Lease Name: M T FRAZIER Well #: 1  
County: COWLEY Total Vertical Depth: 3030 feet

Operator License No.: 33277  
Op Name: COOPER, ALBERT L. DBA COOPER SER  
Address: PO BOX 381  
WINFIELD, KS 67156

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		2950		
PROD	5.5	3030	950	200 SX
SURF		220		
SURF	8.625	250		150 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 08/28/2013 8:00 AM  
Plug Co. License No.: 33277 Plug Co. Name: COOPER, ALBERT L. DBA COOPER SERVICE CO.  
Proposal Rcvd. from: ALBERT L. COOPER Company: COOPER SERVICE CO Phone: (316) 204-0072

Proposed Plugging Method: AS PER KCC RULES & REGS/ SAND @ 2840, & 5 SKS, CIRC. CEMENT 300'-0'.

Plugging Proposal Received By: JEFF KLOCK WitnessType: PARTIAL  
Date/Time Plugging Completed: 09/27/2013 2:45 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

9-6-2013, DUMPED SAND, SANDED WELL BACK @ 2810', DUMP BAILED 5 SXS CEMENT ON TOP. 9-9-2013, TAGGED CEMENT @ 2743'. CUT CASING @ 1200', 1000', & 950'. LAYED DOWN 27 JOINTS 5 1/2" CASING (950'). 9-18-2013, RIH W/TBG @ 300', COOPER SERVICE ESTABLISHED CIRCULATION & PUMPED 80 SXS 60/40 POZMIX. SDON. TAGGED CEMENT PLUG @ 110'. BAILED HOLE DRY & DUMPED 15 SXS CLASS A COMMON. 9-26-2013, TAGGED CEMENT PLUG @ 75'. 9-27-2013, RIH W/TBG @ 75', COOPER SERVICE ESTABLISHED CIRCULATION, & PUMPED 25 SXS 60/40 POZMIX TO SURFACE. CEMENT CIRCULATED. PLUG DOWN 2:45 PM 9-27-2013. DANIELS READY MIX CEMENT TICKET #029096, & 029146.

Perfs:

Top	Bot	Thru	Comments
2897	2900	CSG	
2888	2904		

Remarks: COMPLIANCE / 10 YR RULE

Plugged through:

District: 02

Signed

DUANE KRUEGER  
09/16/14  
(TECHNICIAN)

KCC WICHITA

DEC 26 2013

RECEIVED