

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-203-20222-00-00  
Spot: SWSWSE Sec/Twnshp/Rge: 1-18S-36W  
4950 feet from N Section Line, 2310 feet from E Section Line  
Lease Name: JACQUE Well #: 1-1  
County: WICHITA Total Vertical Depth: 5000 feet

Operator License No.: 33514  
Op Name: JO-ALLYN OIL CO., INC.  
Address: PO BOX 446  
LAVERNE, OK 73848

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	478		WITH 350 SX CMT

Well Type: DH UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 12/15/2013 11:30 AM  
Plug Co. License No.: 33793 Plug Co. Name: H2 DRILLING LLC  
Proposal Revd. from: \_\_\_\_\_ Company: \_\_\_\_\_ Phone: \_\_\_\_\_

Proposed Plugging Method: 1ST PLUG AT 2460' WITH 50 SX CMT. 2ND PLUG AT 1450' WITH 80 SX CMT. 3RD PLUG AT 725' WITH 50 SX CMT. 4TH PLUG AT 508' WITH 50 SX CMT. 5TH PLUG AT 60' WITH 20 SX CMT. 6TH PLUG TO CIRCULATE RAT HOLE WITH 30 SX CMT. 7TH PLUG TO CIRCULATE MOUSE HOLE WITH 20 SX CMT.

Plugging Proposal Received By: NATHAN WILLIS WitnessType: NONE  
Date/Time Plugging Completed: 12/15/2013 1:30 PM KCC Agent: NATHAN WILLIS

Actual Plugging Report:

1ST PLUG AT 2460' WITH 50 SX CMT. 2ND PLUG AT 1450' WITH 80 SX CMT. 3RD PLUG AT 725' WITH 50 SX CMT. 4TH PLUG AT 508' WITH 50 SX CMT. 5TH PLUG AT 60' WITH 20 SX CMT. 6TH PLUG TO CIRCULATE RAT HOLE WITH 30 SX CMT. 7TH PLUG TO CIRCULATE MOUSE HOLE WITH 20 SX CMT.

Perfs:

Remarks: USED 60/40 POZMIX 4% GEL 1/4# FLO SEAL BY ALLIED.

Plugged through: DP

District: 01

RECEIVED  
DEC 17 2013  
KCC DODGE CITY

Signed Nathan Willis  
01/17/14 (TECHNICIAN)

KCC WICHITA

DEC 19 2013

RECEIVED

Form CP-2/3

*Handwritten signature*