

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-081-20007-00-00
Spot: SESW Sec/Twnshp/Rge: 35-28S-34W
660 feet from S Section Line, 1980 feet from W Section Line
Lease Name: REIMER WHITE B Well #: 1
County: HASKELL Total Vertical Depth: 4746 feet

Operator License No.: 33094
Op Name: CIMAREX ENERGY CO.
Address: 202 S. CHEYNNE AVE STE 1000
TULSA, OK 74103

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		1900		
CIBP		4150		WITH 2 SX CMT
PROD	5.5	4745	0	WITH 225 SX CMT
SURF	8.625	790		WITH 475 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 12/19/2013 10:30 AM
Plug Co. License No.: 34069 Plug Co. Name: BASIC ENERGY SERVICES, LP
Proposal Rcvd. from: WADE LOEPPKE Company: CIMAREX ENERGY Phone: (620) 287-0024

Proposed Plugging Method: CIBP @ 4150' WITH 2 SX CMT. CIBP @ 1900'. PERFORATE AT 1800'. RUN RETAINER TO 1400'. EST. INJECTION INTO PERFS. PUMP 20 BBLs GEL OR MUD FOLLOWED BY 50 SX CMT W/100# HULLS. DISPLACE WITH 6 BBLs WATER. PERFORATE @ 750'. BREAK CIRCULATION IN CASING. FILL 5 1/2" CASING & ANNULUS TO SURFACE.

Plugging Proposal Received By: KEN JEHLIK Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 12/19/2013 12:10 PM KCC Agent: DANIEL SELLERS

Actual Plugging Report:

CIBP @ 4150' WITH 2 SX CMT. CIBP @ 1900'. PERFORATED 4 HOLES AT 1800'. RAN RETAINER TO 1400'. INJECTED 20 BBLs GEL FOLLOWED BY 50 SX CMT WITH 100# HULLS. DISPLACED WITH 6 BBLs WATER. PERFORATED 4 HOLES AT 750'. BROKE CIRCULATION IN CASING. FILLED 5 1/2" CASING & ANNULUS TO SURFACE USING 220 SX CMT.

Perfs:

Top	Bot	Thru	Comments
4686	4689		
4498	4500		
4170	4174		

Remarks: **COMPLIANCE ISSUE: DENIED TA SI 10 YRS** USED 60/40 POZMIX 4% GEL BY BASIC ENERGY.

Plugged through: TBG

District: 01

Signed

Daniel Sellers
01/16/14
(TECHNICIAN)

RECEIVED

DEC 31 2013

KCC DODGE CITY

KCC WICHITA

JAN 07 2014

RECEIVED

Form CP-2/3

AM