

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

**KCC WICHITA**

**KANSAS CORPORATION COMMISSION  
OIL & GAS CONSERVATION DIVISION  
WELL PLUGGING RECORD  
K.A.R. 82-3-117**

**JAN 29 2014** Type or Print on this Form  
Form must be Signed  
All blanks must be Filled

Form CP-4  
March 2009  
Form must be Signed  
All blanks must be Filled

**RECEIVED**

OPERATOR: License #: 33277  
 Name: Cooper Service Co.  
 Address 1: PO Box 381  
 Address 2: \_\_\_\_\_  
 City: Winfield State: Ks. Zip: 67156 + \_\_\_\_\_  
 Contact Person: Albert Cooper  
 Phone: (316) 204-0072  
 Type of Well: (Check one)  Oil Well  Gas Well  OG  D&A  Cathodic  
 Water Supply Well  Other: \_\_\_\_\_  SWD Permit #: \_\_\_\_\_  
 ENHR Permit #: \_\_\_\_\_  Gas Storage Permit #: \_\_\_\_\_  
 Is ACO-1 filed?  Yes  No If not, is well log attached?  Yes  No  
 Producing Formation(s): List All (If needed attach another sheet)  
2897 Depth to Top: 2900 Bottom: 2950 T.D. \_\_\_\_\_  
 \_\_\_\_\_ Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_  
 \_\_\_\_\_ Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_

API No. 15 - 035-23208-00-01  
 Spot Description: SW/NE/SW/NE  
SW/NE/SW/NE Sec. 21 Twp. 32 S. R. 4  East  West  
3,597 Feet from  North /  South Line of Section  
1,682 Feet from  East /  West Line of Section  
 Footages Calculated from Nearest Outside Section Corner:  
 NE  NW  SE  SW  
 County: Cowley  
 Lease Name: MT Frazier Well #: 1  
 Date Well Completed: April 21, 1997  
 The plugging proposal was approved on: Sept. 1, 2013 (Date)  
 by: KLOR (KCC District Agent's Name)  
 Plugging Commenced: 9/6/13  
 Plugging Completed: 9/27/13

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface, Conductor & Production)			
Formation	Content	Casing	Size	Setting Depth	Pulled Out
Surface			8.625	250	0
Bartilville			5.5	3030	950

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

9/6/13, Dumped sand, sanded well back @ 2810, Dumped bailed 5 sk.s cement on top. 9/9/13, tagged cement @ 2743'. Cut casing @ 1200', 1000', 950'. Layed down 27 jt.s of 5 1/2" casing(950'). 9/18/13 RIH w/tbg @300', Cooper Service established circ. & pumped 80 sk.s 60/40 Pozmix. Tagged cement plug @ 110'. Bailed hole dry & dumped 15 sk.s class A common. 9/26/13 tagged cement plug @ 75'. 9/27/13, RIH w/tbg. @ 75', Cooper Service established circ. & pumped 25 sk.s 60/40 Pozmix to surface. Cement circ.. Plug down. 2:45 PM 9/27/13. Daniels Ready Mix Cement Ticket # 029096 & 029146

Plugging Contractor License #: 33277 Name: Cooper Service Co.  
 Address 1: PO Box 381 Address 2: \_\_\_\_\_  
 City: Winfield State: Ks. Zip: 67156 + \_\_\_\_\_  
 Phone: (316) 204-0072  
 Name of Party Responsible for Plugging Fees: Albert Cooper  
 State of Ks. County, Cowley, ss.  
Cooper Service Co.  Employee of Operator or  Operator on above-described well,  
 (Print Name)

being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

Signature: Albert Cooper

48