

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

KCC WICHITA

JAN 29 2014

RECEIVED

Form CP-4
March 2009
Type or Print on this Form
Form must be Signed
All blanks must be Filled

OPERATOR: License #: 33277
Name: Cooper Service Co.
Address 1: PO Box 381
Address 2: _____
City: Winfield State: Ks. Zip: 67156 + _____
Contact Person: Albert Cooper
Phone: (316) 204-0072
Type of Well: (Check one) Oil Well Gas Well OG D&A Cathodic
 Water Supply Well Other: _____ SWD Permit #: _____
 ENHR Permit #: _____ Gas Storage Permit #: _____
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (If needed attach another sheet)
3165' Depth to Top: 3175' Bottom: 3255' T.D. _____
_____ Depth to Top: _____ Bottom: _____ T.D. _____
_____ Depth to Top: _____ Bottom: _____ T.D. _____

API No. 15 - 035-24247.00.00
Spot Description: N2/SE/SW
N2 SE SW Sec. 9 Twp. 33 S. R. 3 East West
900-1153 Feet from North / South Line of Section
1,980-3152 Feet from East / West Line of Section
KCC GPS'd
Footages Calculated from Nearest Outside Section Corner:
 NE NW SE SW
County: Cowley
Lease Name: McClung Well #: 9-1
Date Well Completed: July 16, 2006
The plugging proposal was approved on: Sept 25, 14 (Date)
by: KLOR (KCC District Agent's Name)
Plugging Commenced: 9/26/13
Plugging Completed: 10/7/13

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface, Conductor & Production)			
Formation	Content	Casing	Size	Setting Depth	Pulled Out
		Surface	8.625	310	0
		Prod.	4.5	3260	1200'

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

9/26/13, Dumped sand, sanded back @ 3115', Dumped bailed 4 sk.s cement on top. Tagged cement @ 3060'. Cut casing @ 2000', 1200'. Layed down 32 jt.s 4.5" casing (1200'). 10/4/13 RIH w/tbg @ 360', Cooper Service established circ & pumped 105 sk.s 60/40 Pozmix to surface. Tagged cement plug @ 95'. 10/7/13 RIH RIH w/tbg @ 90' Cooper Service established circ & pumped 30 sk.s 60/40 Pozmix to surface. Cement circ., plug down 3PM 10/7/13. Daniels Ready Mix cement ticket # 029217, 029224.

Plugging Contractor License #: 33277 Name: Cooper Service Co.
Address 1: PO Box 381 Address 2: _____
City: Winfield State: Ks. Zip: 67156 + _____
Phone: (316) 204-0072
Name of Party Responsible for Plugging Fees: Albert Cooper
State of Ks. County, Cowley, ss.
Cooper Service Co. Employee of Operator or Operator on above-described well,
(Print Name)

being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

Signature: Albert Cooper

X