

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

KCC WICHITA
JAN 29 2014
Form CP-4
March 2009
Type or Print on this Form
Form must be Signed
All blanks must be Filled

OPERATOR: License #: 33277
Name: Cooper Service Co.
Address 1: PO Box 381
Address 2: _____
City: Winfield State: Ks Zip: 67156 + _____
Contact Person: Albert Cooper
Phone: (316) 204-0072
Type of Well: (Check one) Oil Well Gas Well OG D&A Cathodic
 Water Supply Well Other: _____ SWD Permit #: _____
 ENHR Permit #: _____ Gas Storage Permit #: _____
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (If needed attach another sheet)
2795' Depth to Top: 2800' Bottom: 3350' T.D. _____
_____ Depth to Top: _____ Bottom: _____ T.D. _____
_____ Depth to Top: _____ Bottom: _____ T.D. _____

RECEIVED
API No. 15 - 035-22183-00-00
Spot Description: SW/NE/SW
SW-NE-SW Sec. 9 Twp. 33 S. R. 3 East West
674 Feet from North / South Line of Section
1,978 Feet from East / West Line of Section
Footages Calculated from Nearest Outside Section Corner:
 NE NW SE SW
County: Cowley
Lease Name: McClung Well #: 1
Date Well Completed: March 28, 1979
The plugging proposal was approved on: Oct. 2nd, 2013 (Date)
by: KLOR Korf (KCC District Agent's Name)
Plugging Commenced: Oct. 15, 2013
Plugging Completed: 10/25/13

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface, Conductor & Production)			
Formation	Content	Casing	Size	Setting Depth	Pulled Out
		Surface	8.625	200	0
		Prod.	4.5	3300	600'

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

RIH w/tbg @ 2780', Cooper Service established circ. & pumped 12 sk.s class A common & displaced in casing. Tagged cement @ 2510'. Cut casing @ 600'. Layed down 16 jt.s 4.5" casing (600'). 10/24/13 RIH w/tbg. @ 360', Cooper Service established circ. & pumped 140 sk.s 60/40 Pozmix . Tagged cement plug @ 105'. 10/25/13 RIH w/tbg. @ 95'. Cooper Service established circ & pumped 30 sk.s 60/40 Pozmix to surface, cement circ. . Plug down 3 PM 10/25/13. Daniels Ready Mix cement ticket # 029354 & 029365.

Plugging Contractor License #: 33277 Name: Cooper Service Co.
Address 1: PO Box 381 Address 2: _____
City: Winfield State: Ks Zip: 67156 + _____
Phone: (316) 204-0072
Name of Party Responsible for Plugging Fees: Albert Cooper
State of Ks. County, Cowley, ss.
Cooper Service Co. Employee of Operator or Operator on above-described well,
(Print Name)

being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God

Signature: Albert Cooper