

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

WELL PLUGGING RECORD

Barber County, Sec. 29 Twp. 34 Rge. 14W (E) (W)

Location as "NE/CNWxSWx" or footage from lines NW NE

Lease Owner Wm. Gruenerwald

Lease Name Alexander Well No. 1

Office Address 35 East Wacker Drive Chicago, Illinois

Character of Well (completed as Oil, Gas or Dry Hole) Gas-depleted

Date well completed \_\_\_\_\_ 19\_\_\_\_

Application for plugging filed \_\_\_\_\_ 19\_\_\_\_

Application for plugging approved \_\_\_\_\_ 19\_\_\_\_


Plugging commenced \_\_\_\_\_ 19\_\_\_\_

Plugging completed December 20, 1962

Reason for abandonment of well or producing formation \_\_\_\_\_

If a producing well is abandoned, date of last production \_\_\_\_\_ 19\_\_\_\_

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well Herman Justus

Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 4743' Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

4742' of 5 1/2" oil string. top perforation at 4670'. Hole sanded to 4378' and 25 sacks cement by Globe Cementing Co. 957' of 8 5/8" surface pipe circulated with cement. Hole filled to 500' with mud, 10' rock bridge and 20 sacks cement. Hole filled to 40' with mud, 10' rock bridge and 10 sacks cement to base of cellar. Recovered 3992' of 5 1/2" pipe.

**RECEIVED**  
STATE CORPORATION COMMISSION

OCT 16 1963  
10-16-63

CONSERVATION DIVISION  
Wichita, Kansas

Name of Plugging Contractor Sargent's Casing Pulling Service  
Address 221 S. 9th St. Liberal, Kansas

STATE OF Illinois, COUNTY OF Cook, ss.  
WILLIAM GRUENERWALD (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) [Handwritten Signature]

(Address) \_\_\_\_\_

SUBSCRIBED AND SWORN TO before me this 14th day of October, 1963

[Handwritten Signature]  
Notary Public.

My commission expires 10-31-64

William Gruenerwald  
 Alexander Well #1  
 Total Depth 4745 Feet  
 Comm. 12/14/57  
 Rotary Comp. 1/5/58  
 Cable Tool Comp. 7/23/58  
 Contractor  
 Patton Drilling Company, Inc.

Location C NW-NE Sec. 29-T34S-R14W  
 Barber County, Kansas.  
 CASING RECORD  
 # 213 Feet of 13 3/8" Casing  
 Cemented with 225 Sack  
 957 Feet of 8 5/8" Casing  
 225 Sacks on Bottom and 25 sacks  
 thru 1" Pipe on Top

Red Bed 810  
 Shale & Shells 1400  
 Salt & Shale 1720  
 Shale & Lime 2570  
 Shale & Shells 2690  
 Shale & Lime 2930  
 Shale & Shells 3050  
 Shale & Lime 3200  
 Lime 3325  
 Shale & Lime 3495  
 Lime 3550  
 Shale & Lime 3680  
 Sand Shale 3780  
 Shale & Lime 3825  
 Sand & Shale 3970  
 Shale & Lime 4047  
 Sand & Lime 4142  
 Lime 4533  
 Shale & Lime 4593  
 Lime 4657  
 Shale & Lime 4693  
 Lime 4745  
 Total Depth 4745

4745 Feet 5 1/2" Casing  
 Cemented with 250 Sacks

**RECEIVED**  
 STATE CORPORATION COMMISSION  
 OCT 16 1963  
 18-16-63  
 CONSERVATION DIVISION  
 Wichita, Kansas

STATE OF Kansas COUNTY Adair ss,

I, the undersigned, being duly sworn, on oath state that the above statement and log is a true and correct record and log of the well drilled at the location above described.

PATTON DRILLING COMPANY, INC.

By Robert W. Patton

Subscribed and sworn to before me this 7th day of October 1963

T. P. Hendrick  
 T. P. Hendrick Notary Public

My Commission expires Oct 4th 1964