

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

Barber County. Sec. C Twp. N/2 Rge. N/2 (E) (W) X

Location as "NE/CNW&SW&" or footage from lines App. C N/2 N/2

Lease Owner Bowers Drilling Company, Inc.

Lease Name Baier B Well No. 1

Office Address 125 No. Market, Suite 1434 Wichita, Kansas 67202

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed 6-6- 19 70

Application for plugging filed 6-6 19 70

Application for plugging approved 6-6 19 70

Plugging commenced 6-6- 19 70

Plugging completed 6-6 19 70

Reason for abandonment of well or producing formation D & A

If a producing well is abandoned, date of last production _____ 19 _____

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes - verbally

Name of Conservation Agent who supervised plugging of this well G. Russell Biberstein Attica, Kansas

Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4793 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Heavy mud to 300' from 4793'
Set plug at 300' w/25 sks. heavy mud to 40'
Cement Plug @ 40' w/15 sks.

RECEIVED
STATE CORPORATION COMMISSION
6-18-70
JUN 18 1970
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Bowers Drilling Company, Inc.
Address 125 North Market, Suite 1434 Wichita, Kansas 67202


STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
Emil E. Bowers (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Emil E. Bowers
125 North Market, Suite 1434, Wichita, Kansas 67202
(Address)

SUBSCRIBED AND SWORN TO before me this 17th day of June, 19 70

My commission expires May 12, 1973

Carol A. Young
Notary Public.



WELL LOG

COMPANY: Bowers Drilling Company, Inc.
 CONTRACTOR: Bowers Drilling Company, Inc.
 FARM: Baier B #1
 LOCATION: Approx. 200' So. of C N/2-N/2
 Section 35-T34S-R14W
 Barber County, Kansas
 COMMENCED: 5-27-70
 COMPLETED: 6- 6-70
 ELEVATION: 1538 Kelly Bushing
 1536 Derrick Floor
 1532' Ground Level

0 - 1600	Red Bed Shale & Shells	Set 8 5/8" csg. @358' w/225 saks
1600 - 2318	Shale & Lime	
2318 - 2590	Lime	
2590 - 4270	Lime & Shale	
4270 - 4746	Lime	
4746 - 4793	Mississippi	
4793	T.D.	

LOG TOPS:	Elgin Zone	3712 (-2172)
	Heebner	3920 (-2382)
	Toronto	3935 (-2397)
	Douglas	3984 (-2446)
	Lansing	4100 (-2562)
	B/Kansas City	4620 (-3082)
	Mississippian	4717 (-3179)
	Log T. D.	4793

RECEIVED
 STATE CORPORATION COMMISSION
 JUN 18 1970
 CONSERVATION DIVISION
 Wichita, Kansas

STATE OF KANSAS)
) SS
 COUNTY OF SEDGWICK)

I, Emil E. Bowers, do hereby certify that the above and foregoing is a true and correct copy of the log of the #1 Baier "B" located Approx. 200' So. of C N/2 N/2 Section 35-T34S-R14W, Barber County, Kansas, as reflected by the files of Bowers Drilling Company, Inc.

Emil E. Bowers
 Emil E. Bowers, President

Subscribed and sworn to before me, a Notary Public, in and for the State of Kansas, this 9th. day of June, 1970.

Carole A. Young
 Carole A. Young, Notary Public

My commission expires May 12, 1973.

