


STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas 67202

WELL PLUGGING RECORD



Locate well correctly on above
Section Plat

Barber County. Sec. 15 Twp. 34S Rge. (E) 14(W)
Location as "NE/CNWxSWx" or footage from lines S/2 S/2 SW/4
Lease Owner McCoy Petroleum Company
Lease Name McBrayer Well No. 2
Office Address 502 Union Center, Wichita, Kansas 67202
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed January 15, 1972
Application for plugging filed January 15, 1972
Application for plugging approved January 15, 1972
Plugging commenced January 15, 1972
Plugging completed January 15, 1972
Reason for abandonment of well or producing formation _____

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well G. R. Biberstein, Attica, Kansas
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4920 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	1022'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Mudded up with heavy mud to 400 feet. Followed by wooden plug, 1/2 sack hulls and 35 sacks cement. Mudded up with heavy mud to 40 feet followed by wooden plug, 1/2 sack hulls and 10 sacks cement to base of well cellar. Plugged rat hole with 2 sacks cement.

RECEIVED
STATE CORPORATION COMMISSION
JAN 18 1972
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Graves Drilling Co., Inc.
Address 505 Union Center, Wichita, Kansas 67202

STATE OF KANSAS, COUNTY OF BUTLER, ss.
John C. Graves (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) John C. Graves
505 Union Center, Wichita, Kansas 67202
(Address)

SUBSCRIBED AND SWORN to before me this 17th day of January, 19 72

Betty Brandt
Betty Brandt Notary Public.

My commission expires May 9, 1975

SP

R O T A R Y D R I L L E R S ' L O G

OPERATOR: McCoy Petroleum Company DRILLING COMMENCED: January 2, 1972
502 Union Center
Wichita, Kansas 67202

CONTRACTOR: Graves Drilling Co., Inc. DRILLING COMPLETED: January 15, 1972
505 Union Center
Wichita, Kansas 67202

CASING RECORD: 25 Jts. 1022' 8-5/8" cemented with 708 sacks LOCATION: McBrayer No. 2
S/2 S/2 SW/4
Section 15-34S-14W
Barber County, Kansas

- 0 - 144 Red bed
- 144 - 760 Shale & shells
- 760 - 1059 Red bed & shale
- 1059 - 1628 Shale & shells
- 1628 - 2260 Shale & lime
- 2260 - 3970 Lime & shale
- 3970 - 4055 Shale & lime
- 4055 - 4203 Shale, sand & limey shale
- 4203 - 4770 Lime
- 4770 - 4817 Lime & shale
- 4817 - 4850 Cherty dolomite
- 4850 - 4920 Lime
- 4920 Rotary Total Depth

RECEIVED
STATE CORPORATION COMMISSION
JAN 18 1972
CONSERVATION DIVISION
Wichita, Kansas

I hereby certify the foregoing statements to be true and correct to the best of my knowledge.

GRAVES DRILLING CO., INC.

By *Phil Graves*
President

STATE OF KANSAS)
) ss.
BUTLER COUNTY)

Subscribed and sworn to before me, a Notary Public, this 17th of January, 1972.

Betty Brandt
Betty Brandt Notary Public

My commission expires:
May 9, 1975