

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
700 Bitting Building
Wichita, Kansas

Barber County. Sec. 15 Twp. 34 Rge. (E) 14 (W)

Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines S1/2 NE, NW.

Lease Owner Aladdin Pet Corp. and Others.

Lease Name Kincade Well No. 1

Office Address Petroleum Bldg. Wichita, Kansas.

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed August 18th 19 49

Application for plugging filed August 17th 19 49

Application for plugging approved August 17th 19 49

Plugging commenced August 18th 19 49

Plugging completed August 18th 19 49

Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

C. D. Stough

Name of Conservation Agent who supervised plugging of this well

Producing formation Depth to top Bottom Total Depth of Well 5478 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
				8 5/8	337ft.	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled with Heavy Rotary Mud to 300 Feet Set Plug with 20 Sacks Cement
Filled with Heavy Rotary Mud to 30 Feet Set Plug with 10 Sacks Cement
to Bottom of Cellar.

8-23-49
AUG 23 1949
STATE CORPORATION
COMMISSION
KANSAS

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to Aladdin Pet Corp. & Others
Address 809 Petroleum Bldg. Wichita, Kansas.

STATE OF Kansas, COUNTY OF Sedgwick, ss.

R. C. Patton (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature)

R. C. Patton

612 Orpheum Bldg. Wichita, Kansas.


(Address)

SUBSCRIBED AND SWORN TO before me this 22 day of August 1949

J. P. Hendrick

Notary Public.

My commission expires October 4th 1952



15-007-00058-0000

Aladdin Petroleum Corp & Others.
Kincade Well #1
Comm: 7/3/49
Comp. 8/18/49
Total Depth 5478
Contractor R. C. Patton Co.,

Located SWc, NE, NW. Section
15, T34S, R14W Barber Co, Kans.
CASING RECORD
8 5/8" Casing at 337 Feet
Cemented with 150 Sacks.

Cellar	8	Shale	5103
Sand	30	Lime & Shale	5200
Red Beds & Shells	337	Lime	5323
Shale & Shells	465	Lime & Shale	5350
Red Shale & Shells	1120	Shale & Sand	5375
Lime & Shale	1345	Broken Lime & Sand	5414
Shale & Shells	1535	Shale & Lime	5435
Salt & Shale	1575	Lime	5478
Lime & Shale	1920	Total Depth	5478
Lime	2390		
Shale	2435		
Lime	2495		
Lime & Shale	2765		
Shale	2875		
Lime & Shale	2955		
Shale	3075		
Lime & Shale	3130		
Shale & Shells	3220		
Lime & Shale	3375		
Lime	3615		
Lime & Shale	3660		
Sahle	3725		
Lime & Shale	3830		
Shale	3900		
Lime & Shale	3955		
Shale	3990		
Shale & Sand	4050		
Lime	4086		
Sand & Shale	4100		
Lime & Shale Brk.	4150		
Sahle	4190		
Lime	4250		
Lime & Sand	4255		
Lime & Shale	4295		
Lime	4350		
Lime & Shale Brk.	4375		
Lime	4500		
Lime & Shale Brk.	4515		
Lime & Shale	4625		
Shale & Sand	4640		
Lime & Shale	4808		
Lime Chert	4831		
Lime	4885		
Shale	4909		
Lime	4955		
Lime Cherty	4982		
Shale	5003		
Lime	5055		

8-23-49
Aug 23 1949

STATE OF Kansas COUNTY OF Adair ss,

I, the undersigned, being duly sworn, on oath state that the above statement and log is a true and correct record and log of the well drilled at the location above described.

R. C. PATTON CO.,

By R. C. Patton

Subscribed and sworn to before me this 29th day of August 1949

J. P. Anderson
Notary Public

My Commission expires Oct 4th, 1952

