

To: 1 120813
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

8-4

API NUMBER 15- 007-20,365-A -00-01
C NW SW, SEC. 36, T 34 S, R 12 W/X
1980 feet from S section line
4620 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 4677
Operator: Cara Ventures, Inc.
Name & Address: P.O. Box 287
Attica, KS 67009-0287

Lease Name Wetz Well # 1 OWWO
County Barber
Well Total Depth 4930 160.22 feet
Conductor Pipe: Size feet
Surface Casing: Size 8 5/8 feet 291

Abandoned Oil Well Gas Well Input Well SWD Well D&A
Other well as hereinafter indicated

Plugging Contractor Pratt Well Service, Inc. License Number 5893
Address P.O. Box 847, Pratt, KS 67124-0847

Company to plug at: Hour: 8 a.m. Day: 4 Month: 8 Year: 19 93
Plugging proposal received from Paul Caragianis
(company name) Cara Ventures, Inc. (phone) 316-722-9575

were: 4 1/2" at 4898', Tools stuck in 4 1/2" casing at 3900'-lost hole
Put 5 sx cement on top of swab at 3900' with dump bailer,
Pump 50 sx cement and displace to 1900', lay down 42 jts. of 4 1/2" casing and pump 50 sx cement
at 330', lay down 7 jts. of 4 1/2" casing and circulate with 10 sx cement at 40'.

Plugging Proposal Received by Case Morris
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part None
Operations Completed: Hour: 12:15 p.m. Day: 4 Month: 8 Year: 19 93

ACTUAL PLUGGING REPORT Put 5 sx cement on top of swab at 3900' with dump bailer,
Pumped 50 sx cement and displaced to 1900',
Layed down 42 jts. of 4 1/2" casing and pumped 50 sx cement at 330',
Layed down 7 jts. of 4 1/2" casing and circulated cement at 40' with 10 sx cement.

RECEIVED
STATE CORPORATION COMMISSION

AUG 11 1993
8-11-93

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 2095' of 4 1/2" casing.
(Additional description is necessary, use BACK of this form.)

(If you observe this plugging.

INVOICED
DATE AUG 18 1993

Signed Diane Rabin
(TECHNICIAN)

8-4 OCT 06 1993 MAR 15 1994