

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-007-22453-01-01
Spot: NWSWNW Sec/Twnshp/Rge: 2-34S-14W
1700 feet from N Section Line, 380 feet from W Section Line
Lease/Unit Name: GORDON A Well Number: 1
County: BARBER Total Vertical Depth: 5300 feet

Operator License No.: 4548
Op Name: ONEOK RESOURCES COMPANY
Address: PO BOX 871
TULSA, OK 74102

Conductor Pipe: Size 20 feet: 50
Surface Casing: Size 8.625 feet: 463 WITH 315 SX CMT
Production: Size 5.5 feet: 5299 WITH 440 SX CMT
Liner: Size feet: \$172.25

Well Type: OIL UIC Docket No: Date/Time to Plug: 09/11/2001 3:35 PM
Plug Co. License No.: 5105 Plug Co. Name: CLARKE CORPORATION
Proposal Rcvd. from: DENNIS HERTEL Company: ONEOK RESOURCES Phone: (316) 672-9388

Proposed Plugging Method: CIBP @ 3500' & 2 SX CMT. 1ST PLUG AT 500' WITH 50 SX CMT & 10 SX GEL. 2ND PLUG AT 250' WITH 40 SX CMT. 3RD PLUG AT 40' WITH 10 SX CMT.

Plugging Proposal Received By: RICHARD LACEY Witness Type: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 09/11/2001 4:45 PM KCC Agent: SCOTT ALBERG

Actual Plugging Report:

PBTD 4825'. PERFS AT 4233-35, CIBP @ 4970'; 4825, CIBP @ 4800; PERFS AT 4704-4708; CIBP @ 4650; 4505-4508, 4464-68, 4205-8, 4300-05; CIBP @ 4190; CIBP @ 4450'; 3986-3991; CIBP @ 3950; 3558-68; CIBP @ 3500'. 1ST PLUG CIBP @ 3500' WITH 2 SX CMT. 2ND PLUG AT 485' WITH 10 SX GEL & 50 SX CMT. 3RD PLUG AT 270' WITH 40 SX CMT. 4TH PLUG AT 0-40' WITH 10 SX CMT. GOOD CIRCULATION THROUGHOUT JOB.

Remarks: USED 60/40 POZMIX 6% GEL BY ALLIED. RECOVERED 2910' OF 5 1/2" CASING.

Plugged through: CSG

District: 01

Signed



(TECHNICIAN)

RECEIVED

SEP 14 2001
9-14-01
KCC WICHITA

INVOICED

DATE

9-14-01

INV. NO.

2002060470

SEP 12 2001

Form 10/20