

To: 1 040360  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

TECHNICIAN'S PLUGGING REPORT

Operator License # 5552

Operator: Gore Oil Company

Name &

Address 125 North Market, Suite 1750

Wichita, KS 67202

11-20  
API NUMBER 15- 007-21,266-~~0000~~  
SW SE NE, SEC. 34, T 34 S, R 12 W/E  
2970 feet from S section line  
990 feet from E section line

Lease Name Alberding Well # 3

County Barber 157.30

Well Total Depth 4840 feet

Conductor Pipe: Size feet

Surface Casing: Size 10 3/4 feet 313

Abandoned Oil Well ☒ Gas Well ☐ Input Well ☐ SWD Well ☐ D&A ☐

Other well as hereinafter indicated

Plugging Contractor Clarke Corporation License Number 5105

Address P.O. Box 187, Medicine Lodge, KS 67104

Company to plug at: Hour: 11 a.m. Day: 20 Month: 11 Year: 19 89

Plugging proposal received from Scott Scheuerman

(company name) Gore Oil Company (phone) 316-263-3535

were: 4 1/2" at 4839' PRTD 4839' Perfs at 4770-80'

1st plug sand back to 4440' and dump 4 sx cement on top of sand through bailer,

2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 10 3/4"

wiper plug and pump 130 sx cement.

Plugging Proposal Received by Steve Pfeifer  
(TECHNICIAN)

Plugging Operations attended by Agent?: All ☒ Part ☐ None ☐

Operations Completed: Hour: 11:30 a.m. Day: 20 Month: 11 Year: 19 89

ACTUAL PLUGGING REPORT 1st plug sanded back to 4440' and dumped 4 sx cement on top of sand bridge with bailer,

2nd plug pumped down 10 3/4" surface pipe with 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, released 10 3/4" wiper plug and pumped 130 sx cement.

Maximum pressure 400 psi and shut in 250 psi.

Remarks: Used 60/40 Pozmix 6% gel by B.J. Titan. Recovered 3700' of 4 1/2" casing. DIVISION  
(If additional description is necessary, use BACK of this form.)

INVOICED

DATE 12-6-89

INV. NO. 26636

Signed Stephen J. Pfeifer  
(TECHNICIAN)