

4-12-88

123

R

1 040082

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-007-21,265-0000

SW NW NE, SEC. 34, T 34 S, R 12 W/8  
4290 feet from S section line  
2310 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5042

Operator: Edmiston Oil Company, Inc.  
Name & Address: 1260 Kansas State Bank Bldg.  
Wichita, KS 67202

Lease Name Alberding Well # 2

County Barber 157.14

Well Total Depth 4835 feet

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 10 3/4 feet 314

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Kelso Casing Pulling License Number 6050

Address Box 347, Chase, KS 67524

Company to plug at: Hour: 9:30 a.m. Day: 12 Month: 4 Year: 19 88

Plugging proposal received from Millard Kelso

(company name) Kelso Casing Pulling (phone) 316-938-2457

were: 4 1/2" at 4834' PBT 4834' Perfs at 4780-90, 4767-73'

1st plug sand back to 4710' and dump 4 sx cement on top of sand through bailer,

2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release

wiper plug and pump 150 sx cement.

Plugging Proposal Received by Steve Durrant (TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 10:15 a.m. Day: 12 Month: 4 Year: 19 88

ACTUAL PLUGGING REPORT 1st plug sanded back to 4710' and dumped 4 sx cement on top of sand through bailer,

2nd plug pumped down 10 3/4" with 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel,

100 lbs. hulls, released 10 3/4" wiper plug and pumped 150 sx cement.

Maximum pressure 550 psi and shut in 400 psi.

Remarks: Used 60/40 Pozmix 6% gel by B.J. Titan. Recovered 3235' of 4 1/2" casing.  
(If additional description is necessary, use BACK of this form.)

INVOICED  
observe this plugging.

DATE 4-26-88

INV. NO. 20446

Signed Stephen J. Pfeifer (TECHNICIAN)