

11-20

1 040359

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 007-21,376-0000
SW NE NE, SEC. 34, T 34 S, R 12 W/E
4290 feet from S section line
990 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5552

Lease Name Alberding Well # 4

Operator: Gore Oil Company

County Barber 156.33

Name & Address 125 North Market, Suite 1750
Wichita, KS 67202

Well Total Depth 4810 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 327

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Clarke Corporation License Number 5105

Address P.O. Box 187, Medicine Lodge, KS 67104

Company to plug at: Hour: 2 p.m. Day: 20 Month: 11 Year: 19 89

Plugging proposal received from Scott Scheuerman

(company name) Gore Oil Company (phone) 316-263-3535

were: 4 1/2" at 4809' PBD 4798' Perfs at 4745-4755'

1st plug sand back to 4400' and dump 4 sx cement on top of sand through bailer,
2nd plug pump 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls,
and 100 sx cement.

Plugging Proposal Received by Steve Pfeifer
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 2:30 p.m. Day: 20 Month: 11 Year: 19 89

ACTUAL PLUGGING REPORT 1st plug sanded back to 4400' and dumped 4 sx cement on top of
sand bridge with bailer,

2nd plug pumped down 8 5/8" with 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel,
100 lbs. hulls and 100 sx cement. (No wiper plug, surface pipe plated with collar
welded in to pump through.)

Maximum pressure 400 psi and shut in 150 psi.

NOV 28 1989

Remarks: Used 60/40 Pozmix 6% gel by B.J. Titan. Recovered 3590' of 4 1/2" casing.
(If additional description is necessary, use BACK of this form.)

INVOICED

DATE 12-6-89

INV. NO. 26637

Signed Stephen J. Pfeifer
(TECHNICIAN)