

3-15-88

1040069

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-007-21,032-0000
SW NW SE, SEC. 34, T 34 S, R 12 W/E
1650 feet from S section line
2310 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5042
Operator: Edmiston Oil Company, Inc.
Name & Address: 1260 Kansas State Bank Bldg.
Wichita, KS 67202

Lease Name Vogel "C" Well # 2
County Barber
Well Total Depth 4850 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 10 3/4 feet 320

15763

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ O&A _____

Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pulling License Number 6050
Address Box 347, Chase, KS 67524

Company to plug at: Hour: 2:30 p.m. Day: 15 Month: 3 Year: 1988

Plugging proposal received from Millard Kelso

(company name) Kelso Casing Pulling (phone) 316-938-2457

were: 4 1/2" at 4849' PBSD 4849' Perfs at 4782-92'

1st plug sand back to 4730' and dump 4 sx cement on top of sand through bailer,
2nd plug pump down 10 3/4" with 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel,
100 lbs. hulls, release wiper plug and pump 150 sx cement.

Plugging Proposal Received by Steve Pfeifer (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 3 p.m. Day: 15 Month: 3 Year: 1988

ACTUAL PLUGGING REPORT 1st plug sanded back to 4730' and dumped 4 sx cement on top of sand through bailer,

2nd plug pumped down 10 3/4" with 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, released wiper plug and pumped 150 sx cement. Filled with cement.

Maximum pressure 450 psi and shut in 300 psi.

RECEIVED
STATE CORPORATION COMMISSION
3-23-88
MAR 23 1988

Remarks: Used 60/40 Pozmix 6% gel by B.J. Titan. Recovered 3400' of 4 1/2" casing.
(If additional description is necessary, use BACK of this Form.)

Observe this plugging.

INVOICED

DATE 3-25-88

REV. NO. 20188

Signed Stephen Pfeifer (TECHNICIAN)