

1 040076

3-30-88

API NUMBER 15-007-21,235-0000

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

SW NE SE, SEC. 34, T 34 S, R 12 W XE

1650 feet from S section line

990 feet from E section line

Lease Name Morton "A" Well # 2

County Barber 157.30

Well Total Depth 4840 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 10 3/4 feet

TECHNICIAN'S PLUGGING REPORT

Operator License # 5042

Operator: Edmiston Oil Company

Name &

Address 1250 Kansas State Bank Bldg.

Wichita, KS 67202

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pulling License Number 6050

Address P.O. Box 347, Chase, KS 67524

Company to plug at: Hour: 3 p.m. Day: 30 Month: 3 Year: 19 88

Plugging proposal received from Millard Kelso

(company name) Kelso Casing Pulling (phone) 316-938-2457

were: 4 1/2" at 4839' PBT 4839' Perfs at 4782-92'

1st plug sand back to 4730' and dump 4 sx cement on top of sand through bailer,

2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 10 3/4"

wiper plug and pump 150 sx cement.

Plugging Proposal Received by Steve Durrant

(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 3:30 p.m. Day: 30 Month: 3 Year: 19 88

ACTUAL PLUGGING REPORT 1st plug sanded back to 4730' and dumped 4 sx cement on top of sand through bailer.

2nd plug pumped down 10 3/4" with 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel,

100 lbs. hulls, released 10 3/4" wiper plug and pumped 150 sx cement.

Maximum pressure 400 psi and shut in 200 psi.

APR 11 1988

4-11-88

Remarks: Used 60/40 Pozmix 6% gel by B.J. Titan. Recovered 3280' of 4" CONSERVATION DIVISION
(If additional description is necessary, use BACK of this form.) Wichita, Kansas

INVOICED
Observe this plugging.

DATE 4-13-88

INV. NO. 20345

Signed Stephen J. Pfeifer (TECHNICIAN)