

1 040070

3-15-88

15-007-21031-00-01

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- Docket #D-21,425

SW SW SE, SEC. 34, T 34 S, R 12 WXB

330 feet from S section line

2310 feet from E section line

Lease Name Vogel "C" Well # 1

County Barber 158.28

Well Total Depth 4870 feet

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 10 3/4 feet 331

TECHNICIAN'S PLUGGING REPORT

Operator License # 5042

Operator: Edmiston Oil Company, Inc.

Name & Address 1260 Kansas State Bank Bldg.

Wichita, KS 67202

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well  D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Kelso Casing Pulling License Number 6050

Address Box 347, Chase, KS 67524

Company to plug at: Hour: 10 a.m. Day: 15 Month: 3 Year: 19 88

Plugging proposal received from Millard Kelso

(company name) Kelso Casing Pulling (phone) 316-938-2457

were: 4 1/2" at 4864' PBD 4864' Perfs at 4798-4808, 4540-44, 4498-4508'

1st plug sand back to 4450' and dump 4 sx cement on top of sand through bailer,

2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release wiper

plug and pump 150 sx cement.

Plugging Proposal Received by Steve Durrant (TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 10:30 a.m. Day: 15 Month: 3 Year: 19 88

ACTUAL PLUGGING REPORT 1st plug sanded back to 4450' and dump 4 sx cement on top of

sand through bailer,

2nd plug pumped down 10 3/4" with 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel,

100 lbs. hulls, and 150 sx cement.

Maximum pressure 400 psi and shut in 200 psi.

Remarks: Used 60/40 Pozmix 6% gel by B.J. Titan. Recovered 3431' of 4 1/2" casing

(If additional description is necessary, use BACK of this form.)

INVOICED (1) (2) (3) (4) (5) (6) (7) (8) (9) (10) (11) (12) observe this plugging.

DATE 3-25-88

INV. NO. 20185

Signed Stephen J. Pfeiffer (TECHNICIAN)

RECEIVED STATE CORPORATION COMMISSION MAR 23 1988

CONSERVATION DIVISION Wichita, Kansas