

To: 1 040361
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- Docket #D-21,119

SW SE SE, SEC. 34, T 34 S, R 12 W/E
330 feet from S section line
990 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5552

Lease Name Morton "A" Well # 1

Operator: Gore Oil Company

County Barber 158.11

Name:

Address 125 North Market, Suite 1750

Well Total Depth 4865 feet

Wichita, KS 67202

Conductor Pipe: Size feet

Surface Casing: Size 10 3/4 feet 330

Abandoned Oil Well Gas Well Input Well SWD Well X O&A

Other well as hereinafter indicated

Plugging Contractor Clarke Corporation License Number 5105

Address P.O. Box 187, Medicine Lodge, KS 67104

Company to plug at: Hour: 10:45 a.m. Day: 21 Month: 11 Year: 1989

Plugging proposal received from Scott Scheuerman

(company name) Gore Oil Company (phone) 316-263-3535

were: 4 1/2" at 4864' CIBP at 4598' Perfs at 4802-08, 4452-4514'

1st plug sand back to 4400' and pump 4 sx cement on top of sand through bailer,

2nd plug pump 4 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hull, release 10 3/4"

wiper plug and pump 130 sx cement.

Plugging Proposal Received by Steve Pfeifer (TECHNICIAN)

Plugging Operations attended by Agent?: All x Part None

Operations Completed: Hour: 11:15 p. Day: 21 Month: 11 Year: 1989

ACTUAL PLUGGING REPORT 1st plug sanded back to 4400' and dumped 4 sx cement on top of sand bridge with bailer,

2nd plug pumped down 10 3/4" with 400 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel,

100 lbs. hulls, released 10 3/4" wiper plug and pumped 130 sx cement.

Maximum pressure 300 psi and shut in 150 psi.

RECEIVED
NOV 28 1989
STATE CORPORATION COMMISSION

Remarks: Used 60/40 Pozmix 6% gel by B.J. Titan. Recovered 3232' of 4 1/2" casing.
(If additional description is necessary, use BACK of this form.)

INVOICED

DATE 12-6-89

INV. NO. 26638

Signed Stephen J. Pfeifer (TECHNICIAN)