

11-21 15-007-21234-00-01

1 040362

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-Docket #D-21,117
SW SW NE, SEC. 34, T 34 S, R 12 W/E
2970 feet from S section line
2310 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5552

Lease Name Alberding Well # 1

Operator: Gore Oil Company

County Barber 156.81

Name & Address 125 North Market, Suite 1750

Well Total Depth 4825 feet

Wichita, KS 67202

Conductor Pipe: Size _____ feet

Surface Casing: Size 10 3/4 feet 310

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well X D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Clarke Corporation License Number 5105

Address P.O. Box 187, Medicine Lodge, KS 67104

Company to plug at: Hour: 9:15 a.m. Day: 21 Month: 11 Year: 19 89

Plugging proposal received from Scott Scheuerman

(company name) Gore Oil Company (phone) 316-263-3535

were: 4 1/2" at 4824' PBD 4822' Perfs at 4758-4768, 3570-3590'

1st plug sand back to 4626' and dump 4 sx cement on top of sand through bailer,
2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 2 sx hulls, and 130 sx cement.

Plugging Proposal Received by Steve Pfeifer
(TECHNICIAN)

Plugging Operations attended by Agent?: All x Part _____ None _____

Operations Completed: Hour: 10 a.m. Day: 21 Month: 11 Year: 19 89

ACTUAL PLUGGING REPORT 1st plug sanded back to 4626' and dumped 4 sx cement on top of
sand bridge with bailer. 2nd plug drove wooden plug to 3590', sanded to 3352' and
put 4 sx cement on top of sand,

3rd plug pumped down 10 3/4" surface pipe with 300 lbs. hulls, 10 sx gel, 50 sx cement,
10 sx gel, 200 lbs. hulls, and 130 sx cement.

STATE CORPORATION COMMISSION

Maximum pressure 225 psi and shut in 100 psi.

NOV 28 1989

Remarks: Used 60/40 Pozmix 6% gel by B.J. Titan. Recovered 3350' of 4 1/2" casing.
(If additional description is necessary, use BACK of this form.)

INVOICED

DATE 12-6-89

INV. NO. 26635

Signed Steve Pfeifer
(TECHNICIAN)